

# Gilbert Bain Hospital - Cladding Remedials

RIBA Stage 1 Report - March 2025



# Executive Summary

This RIBA Stage 1 Report aims to capture the Strategic and Initial Briefing Items for Gilbert Bain Hospital Cladding Remedials and decant requirements. It covers various key topics including the Project Vision, Client's Objectives, Site Information, Facade Replacement Methodology and Project Risks. Decant Options at Feasibility Stage are explored and presented alongside Structural and Services input and Initial Cost Plans.


The briefing content has in part been provided from a conditional survey of the facade and decant options have been developed with the client, key stakeholders and design team. This initial Concept Stage of work has seen Threesixty, with the Design Team, undertaking a review of the design opportunities and improvements, alongside the technical aspects of achieving a full re-clad of an existing building within a sensible budget allowance.

The intent is that this RIBA Stage 1 level design exercise should provide the Client with a strategy for a phased decant to accommodate the cladding replacement, together with a review of cladding options and buildability for the facade replacement works.

This document contains the appropriate level of drawing, schedules and diagrams to convey the proposed decant options, as well as supporting elevational & detail drawings which will assist the project QS in preparing a preliminary cost appraisal for the overall re-cladding strategy.



Gilbert Bain Aerial Image



# Contents

|           |  |           |
|-----------|--|-----------|
|           | <b>Executive Summary</b>                   | <b>02</b> |
| <b>01</b> | <b>Strategic Brief</b>                     | <b>04</b> |
|           | 1.1 The Project Vision                     | 05        |
|           | 1.2 Key Information and Objectives         | 06        |
| <b>02</b> | <b>Existing Site Information</b>           | <b>08</b> |
|           | 2.1 Site Context                           | 09        |
|           | 2.2 Site Existing Building                 | 10        |
|           | 2.3 Site Constraints                       | 12        |
| <b>03</b> | <b>Initial Project Brief</b>               | <b>13</b> |
|           | 3.1 Building Fabric                        | 14        |
|           | 3.2 Maintaining Services                   | 16        |
|           | 3.3 Department Decant                      | 17        |
| <b>04</b> | <b>Cladding Study</b>                      | <b>18</b> |
|           | 4.1 Identified Repairs                     | 19        |
|           | 4.2 Cladding Comparisons                   | 22        |
|           | 4.3 Cladding Typical Details               | 23        |
|           | 4.4 Structural Considerations              | 25        |
|           | 4.5 Mechanical & Electrical Considerations | 26        |
|           | 4.6 Advisor Contractor Considerations      | 27        |
| <b>05</b> | <b>Affected Areas</b>                      | <b>28</b> |
|           | 5.0 Stakeholder Engagement                 | 29        |
|           | 5.1 Maternity                              | 30        |
|           | 5.2 Renal                                  | 31        |
|           | 5.3 Ward 3                                 | 32        |
|           | 5.4 Clinical Skills                        | 33        |
|           | 5.5 Chemo                                  | 34        |
|           | 5.6 Outpatients                            | 35        |
|           | 5.7 ECG                                    | 36        |
| <b>06</b> | <b>Decant Options</b>                      | <b>37</b> |
|           | 6.1 Department Options                     | 38        |
|           | 6.2 Decant Solutions                       | 45        |
|           | 6.3 Temporary Accommodation                | 49        |
| <b>07</b> | <b>Appendices</b>                          | <b>50</b> |



1


**Strategic  
Brief**

# The Project Vision

Due to structural failures identified in Mott MacDonald's Report on Condition of External Walls published in Dec '24, NHS Shetland are looking to replace the façades of selected elevations of the Gilbert Bain Hospital. The outer leaf of some walls has begun to lean away from the structure causing cracking on the facade and water ingress in the wards. Repair of these façades will improve the internal environment for staff and patients, increasing comfort, reducing drafts and long standing issues with water ingress.

Our Stage 1 exercise shall explore the existing site conditions and constraints, identify departments impacted, work with stakeholders to consider pros and cons of feasibility options for phased (or whole) decants, develop phasing diagrams and decant plans, develop a preferred approach to a typical wall build up (as far as reasonably practical at this early stage) and area extents for costing (by others), working with the Team to consider buildability to help inform the outline programme.

The overall key deliverables for the Team is the preparation and delivery of a **Costed Feasibility Study** that explores the options for **Phasing and Decant**, as well as outline proposals for new **Cladding**. This information shall be to a suitable level to convey a 'Roadmap' for the project but also robust enough to allow a costing exercise to be undertaken by Thomson Gray.



Existing Facade Photographs

## 1.2 Objectives and Key Information

The objective of this report is to provide output to a **RIBA Stage 1 - Preparation and Briefing** level. It is important to recognise that this Stage of work is not a design stage. This stage is about layering detail and requirements into the Project Brief, before the design process commences at Stage 2.

The content in this section of the report has been developed from continuous information exchanges, workshops and meetings where we have interrogated and challenged the Brief. This is to ensure the project has the correct foundation on which to build upon. A Brief that is aligned with the Client's Strategic Objectives is critical to the success of the subsequent design orientated stages of a Project.

The following key outputs are provided in this Stage by the Design Team members (in conjunction with NHS Shetland's input) :

### Architectural

Strategic Project Brief.  
Initial Project Brief.  
Cladding Study  
Decant Schedules of Accommodation  
Decant Options

### Structural

Stage 1 Report on Condition of External Walls.

### M&E Services

Preliminary Report on Proposed External Cladding Installation Interface with M&E Services

### PM / Cost Services

Strategic Project Programme  
Risk Register  
Stage 1 Initial Cost Plan

### Advising Contractor

Draft Construction Programme  
Buildability / Sequencing Report

### Client Team

Client:  
NHS Shetland  
Key Contacts:  
David Wagstaff - Project Director  
Paul Nadin - Project Manager  
Christina McDavitt - Project Clinical Lead  
Michelle Wikinson - Senior Infection Control  
Department Representatives:  
Amanda McDermott - Chief Nurse (Acute + Specialist)  
Janice Irvine - Senior Charge Midwife

### Client's Agent

Hub North / Thomson Gray  
Key Contacts:  
Fraser Innes - Place & Partnership Director  
Stuart Findlay - Project Manager  
Ross Lovatt - Cost Manager

### Design Team

Architect  
Threesixty Architecture  
Key Contacts:  
Gillian Allan - Project Director  
Giovanni Pesiri - Project Architect

### Structural Engineer

Mott MacDonald  
Key Contacts:  
Neil Pearson

### Services Engineer

Callidus Design Ltd.  
Key Contacts:  
Daniel Brady - Project Director  
Gary Speirs - Mechanical Engineer  
Stewart Brown - Electrical Engineer

### Advising Contractor

Robertson Construction Group  
Key Contacts:  
Graeme Lawrie  
John McHardy

### Programme

Full Project - Refer to Thomson Gray Programme within Appendices for Key Dates  
Next Stage - NHS Shetland / Hub North to instruct team to progress to RIBA Stage 2 following review and approval of this Stage 1 Report and preferred decant route.

### Project Budget

Costing information to be provided by Thomson Gray as agreed with NHS Shetland / Hub North

### Project Reporting

Reporting to follow RIBA Plan of Work Stages for both the Recladding and Decant works, supported by end of stage Cost Plans. For speed, the Stage 2 Cladding Study is to progress during the 2-week Client Sign Off period at the end of Stage 1, with instruction to proceed through to completion of Stage 4b within 2 weeks of the issue of the Stage 1 Report and Cost Plan.

### Stakeholder Engagement

Stakeholder Engagement to occur at RIBA stages 1 & 2. Approval gateways to occur at end of Stage 1 and Stage 2. Stages 3 and 4 will be progressed as one scope of service from the Design Team.

### Procurement Route

As of at the end of Stage 1, it is envisaged a Principal Contractor will be appointed to manage the project as a whole, via Hub North's supply chain partners. The project's procurement is likely to be split with a local contractor undertaking the enabling works for the Decant proposals, The Principal Contractor, through the engagement of a specialist cladding contractor, will undertake the contractor design and installation of the recladding and elevational repairs, whilst NHS Shetland will procure the temporary accommodation via the Scottish Government and NHSScotland supply chain partners. The forms of contract to be confirmed.

### Procedures

CAD  
Threesixty to use CAD to deliver the Project. We will issue our information in PDF/CAD to the consultant team as required.

### Statutory Applications

There will be a requirement for Planning and Building Warrant Approval. The number of applications for each will be dependant on the preferred option for the Department Decants.

Following the formal submission of a pre-application enquiry to Shetland Islands Council Planning Department, they have confirmed that as the decant accommodation is likely to require more than 100sqm of temporary accommodation, and the recladding works are at a height of more than 4m above ground floor level, both will be subject to the requirement for full Planning Permission.

Following a pre-application consultation with Shetland Islands Council Building Standards, they advised the temporary accommodation will need a Building Warrant but that these works could be considered via the Limited Life Warrant application process (for buildings with a life of less than 5 years). They advised separate warrant applications would be advisable for 1. The enabling works, 2. The temporary decant accommodation and 3. The Recladding works to enable a more efficient approval process.

The correspondence received from both Departments is included in this report's appendices.

### SHTM/SHBN Compliance

The existing Gilbert Bain Hospital does not comply with many of the current NHS Technical Standards and guidelines and long term, there is an identified requirement to replace the building with a fully compliant new facility. As such, for the purposes of this Feasibility Study, any temporary spaces will equal or better the space standards currently provided in the Hospital. Any derogations to the HTM Guidelines will require to be agreed by NHS Assure

### Environmental Targets & Accreditations

Due to the age of the existing building, the temporary nature of the decant, and the long-term aspiration for a new Hospital, no specific environmental targets have been set for this project.

## 1.2 Objectives and Key Information Project Management

### Programme

Thomson Gray Project Manager has, in conjunction with the Client and Design Teams, prepared a Project Programme to identify detailed Pre-Construction tasks as well as general allowances for the construction period of the works. GBH Cladding, Master Programme, 25-03-2025, Rev 5 is located within the appendices of this report for reference.

### Project Risk Register


Thomson Gray Project Manager has, in conjunction with the Client and Design Team, prepared a Project Risk Register which identifies risks which may impact the Project. Several meetings have taken place to inform the register namely:

- Risk Register Workshop- 27-02-2025
- NHS Programme Board and Risk Management Group- 12-03-2025
- PEP and Risk Register Meeting- 14-03-2025

From these meetings, wherever possible, mitigations have been noted and 'GBH Cladding Risk Register 25-03-2025 Rev 2' is located within the appendices of this report for reference. This register is a live document which will continue to be reviewed and updated as the Project progresses.

### Cost Plan

Thomson Gray Cost Consultant has prepared a Stage 1 Cost Plan: Cladding Remedials - Cost Estimate March 25 rev B that should be read in conjunction with this Report and separate reports prepared by the Structural Engineer and Services Engineer. The estimate has been prepared to assess the likely construction costs associated with the emergency repair work associated with the cladding / envelope of the 4 storey and 3 storey buildings on the Gilbert Bain Hospital Campus, Lerwick. A list of assumptions and exclusions are contained within the report but the works are planned to be carried out in phases as it is assumed the hospital will remain functional throughout. Temporary decant facilities and enabling works to facilitate the project have been included in the overall estimate, with allowances for professional fees, internal costs, optimism Bias and Inflation included.





2

**Existing  
Site  
Information**

## 2.1 Site Context

### Site Address

Gilbert Bain Hospital  
 South Road  
 Lerwick  
 ZE1 0TB  
 Shetland

### Site Ownership

The site is wholly owned by the Client, NHS Shetland. The site plan opposite highlights the red line boundary to the site.

The hospital is surrounded by residential dwellings to the west, north west and north east. Cairnfield Rd runs along the south boundary and provides the main access to the site for staff, patients and emergency vehicles.

The main service access to the site is off Gilbertson Road to the North East. South Road runs along the south western boundary of the site with a variety of commercial properties opposite including Lerwick Health Centre (also owned by NHS Shetland).

### Site Boundaries

NHS Shetland have provided a legal title plan which identifies the ownership boundaries. There are no known legal entitlements or rights of access across the site that we have been made aware of.

There are HV cables and district heating pipework running below the carpark in the far western part of the site.

### Site Access

The main vehicular access to the site is from Cairnfield Road, off South Road. There are 2 access points to the site, with both accessible to Staff and patients, Emergency vehicles use the furthest west access point on Cairnfield Road for A&E Traffic and a one way system operates with site exit closer to the South Road end of Cairnfield Road.

The entrance / exit off Gilbertson Road provides access for staff and patients with a service road running along the rear of the hospital which serves the pharmacy and deliveries courtyard as well as the laundry and plant outbuildings.

### Site Surveys

A site wide topographical survey was recently carried out (May 2024) and we are in receipt of this drawing in CAD and PDF format.

There are several below ground services drawings available and depending on the extent of land required for decant accommodation, further below ground investigations may be required.

Furthermore a digital survey of the hospital elevations was carried out by others and CAD drawings were provided in May 2024.

The lack of below ground survey information is highlighted as a risk item and moving into Stage 3 we would recommend surveys are commissioned to support the next stages of design; e.g:

- Geo Technical
- Environmental
- Archaeological (if appropriate)


The existing Asbestos Risk register suggests there may be asbestos present in some affected areas. An updated Asbestos survey should also be carried out once the extent of the decant works has been confirmed.

For this stage we have worked from CAD OS information, digital elevations provided by Malcolm Hughes Chartered land surveyors and updated record plans prepared by Threesixty Architecture to consolidate all recent alterations.



## 2.2 Existing Building Information Plans

The new Gilbert Bain Hospital was first opened in 1961 comprising the furthest east four storey admin block, the Theatres, with wards 1 and Ronas ward above. The Phase 1 extension was built in 1989 comprising a 4 storey block containing key departments including A&E, Xray, Dental, and the main access corridor at ground floor, with wards located on the first and second floors above, with plant rooms on the top floor all connected to the original building via a two-storey link corridor. In 2001, a ground floor extension was built to wrap around the original Phase 1 building and this accommodates the current Outpatients Department. Most recently in 2023, a single storey extension containing a new MRI Facility was installed at the far western end of the clinics' corridor.




Ground Floor Plan



Second Floor Plan




First Floor Plan



Third Floor Plan

## 2.2 Existing Building Information Elevations

Given the way in which the Hospital Campus has developed over the last 65 years, there are 48 elevations forming the entire envelope of the building. Intermittent water ingress around the southern facing elevations of the hospital has been investigated to varying degrees, and despite numerous repairs over the years, including a remedial parapet flashing being installed with successful results at some of the elevations, the continued focus has been on elevations 38 to 44. The focus of this Stage 1 report is therefore on those identified elevations and we have extracted them from a recent digital survey displayed opposite.




Elevation 36




Elevation 37



Elevation 38




Elevation 39




Elevation 40




Elevation 41



Elevation 42



Elevation 43



Elevation 44



## 2.3 Site Constraints

### Site Location

The hospital site is very constrained with low rise housing backing onto the rear boundaries. Various services outbuildings pepper the rear service access road with pedestrian escape routes threading through these areas. The site falls away from west to east, dropping a storey in height across the site, with split level parking to all available land wrapping around the main building. Blue light vehicular access is required to be maintained at all times at the front of the hospital.

### Potential Decant Locations

Two sites have been identified as potential decant zones, both of which impact on parking provisions. Site A - directly in front of the recent MRI extension has potential to link into the main building via the MRI link corridor. Site B - previously used for the Mobile Theatre Unit, this zone could provide space for a mobile stand alone clinical service such as Renal or Chemo, or corridor compound.

### Site Entrances

As noted previously there are 2 existing access points to the site, and 1 exit only point. The one way vehicular access and route around the upper car park will be maintained throughout.


All 3 points must remain available throughout the duration of the works with emergency vehicles able to drop off / pick up at the main entrance.

### Parking

Visitor / Staff parking is very limited on the site and will be reduced further during the works for the contractor compound and decant accommodation. No additional parking can be provided on site.

### Existing Services

The land identified as a buildable zone is known to have various underground services from the rear outbuildings to the sub station and beyond to Cairnfield Road. This includes underground HV cables and District Heating pipework. The locations of these will need clarified as a preferred site layout and building footprint is identified.





# 3 | Initial Project Brief

### 3.1 Extent of Works Building Fabric

NHS Shetland became concerned with defects in the east elevation wall of the 4 storey tower element of the main building at the Gilbert Bain Hospital following years of intermittent water ingress which had intensified in February 2024 following a prolonged period of south easterly gales accompanied by heavy rain. Mott MacDonald was instructed to inspect the walls of the Phase 1 construction in March 2024 and to inspect cores taken in the outer leaf blockwork between September and October 2024. Their findings are recorded in their Condition Survey Report dated December 2024 which identified various degrees of remedial work required. Mott MacDonald's report has led to the commissioning of this Stage 1 Study.

Subsequent to the initial condition report, and with the recent installation of scaffold around these elevations, further investigations can be commissioned, to develop a detailed scope of works, but for now 2no potential options have been identified:


**Option 1**

Elevations 36 and 37 require some areas of bossed render to be identified and replaced.


Elevations 38 and 39 Remedial works to prevent water ingress should be undertaken as required including provision of new lintels, cills, movement joints and render stop beads. (extent to be confirmed following further Structural Engineer review)

Elevations 40 to 44 require the complete dismantling of the outer leaf of the cavity walls and removal of existing windows. Replacement cladding spanning between the reinforced concrete columns with new insulation is to be installed together with new windows throughout.

Elevation 36




Elevation 37




| EXTENT OF REPAIRS |   |
|-------------------|---|
|                   | Full Facade Replacement   |
|                   | Replace Lintels and Cills, Replace movement joints & render beads     |
|                   | Identify and Replace Areas of Bossed Render only                      |
|                   | Render removed, overcladding to cavity walls, replace lintels & cills |

Elevation 38




Elevation 39




Elevation 40




Elevation 41



Elevation 42



Elevation 43



Elevation 44



# 3.1 Extent of Works Building Fabric

## Option 2


Elevations 36 and 37 require some areas of bossed render to be identified and replaced.

Elevations 38 and 39 require all existing render to be removed from the outer leaf of blockwork, and a new rainscreen cladding system is to be installed, spanning between reinforced columns with replacement of cills and lintels throughout.

Elevations 40 to 44 require the complete dismantling of the outer leaf of the cavity walls and removal of existing windows. Replacement cladding spanning between the reinforced concrete columns with new insulation is to be installed together with new windows throughout.

Whether we proceed with Option 1 or 2 for the external elevational repairs, both options will have a significant impact on the associated internal spaces. Scaffolding on the roof of the Outpatients building has already been erected to shroud the 4 storey Phase 1 building. Internal propping to the inner leaf blockwork walls will be required for the period when the existing inner leaf alone is exposed to wind loading. Because of this, affected areas have been identified and this Stage 1 Report has also had to consider how the identified external repairs can be implemented whilst maintaining critical healthcare services throughout the duration of the works.

Elevation 36




Elevation 37




| EXTENT OF REPAIRS |   |
|-------------------|---|
|                   | Full Facade Replacement   |
|                   | Replace Lintels and Cills, Replace movement joints & render beads     |
|                   | Identify and Replace Areas of Bossed Render only                      |
|                   | Render removed, overcladding to cavity walls, replace lintels & cills |

Elevation 38




Elevation 39




Elevation 40




Elevation 41



Elevation 42



Elevation 43




Elevation 44



### 3.2 Extent of Works Maintaining Services

The 4 storey tower is a part of the 1960s Phase 1 construction and includes plant rooms at third floor, a General Medical Ward 3 on the second floor and the Maternity and Renal departments at first floor. At ground floor the newer 1980s Outpatients Department was built around the original building, which includes the Dental Department, ECG and the main corridor of the hospital providing access to every department via the main lift and stair core.


Following several workshops with Clinical Stakeholders, the impact of the external repairs has been deemed too obtrusive to allow them to deliver continuous clinical care in a safe, warm, quiet and clean environment for the duration of the works. Therefore as a minimum, alternative temporary accommodation must be provided for the directly impacted departments located on first floor (Maternity and Renal) and second floor (General Medical Ward 3). In addition, there are concerns that with lengthy exposure of the internal block face of Elevations 40-44, and poorly installed cavity trays at the junction with the Ground Floor roof, water ingress could increase to ground floor departments including Outpatients, Dental and ECG and the main Hospital access corridor. If this were to materialise, these departments may also need to be temporarily displaced. The potential impacted areas are highlighted on the plans opposite.




Ground Floor Plan



Second Floor Plan



First Floor Plan




Third Floor Plan

### 3.3 Department Decant

Through dialogue with Clinical Stakeholders, some spaces in other locations in the Hospital have been identified as potentially suitable for decant, if this were to ensure co-localities / dependencies of departments can be maintained, namely Chemotherapy and Clinical Skills on the second floor, closed beds on Ward 1 on the first floor and SDEC on the ground floor. The diagram opposite, identifies all potential departments considered for decant within this report and further details can be found in Section 5 Affected Areas.





**4**






**Cladding  
Study**

## 4.1 Identified Repairs Elevations 40-44

In Mott MacDonald's condition report Elevations 40-44 have been identified as suffering outward displacement, with significant cracking at the wall head which has raised concerns over the stability of the blockwork. Wall ties are loose at points and the tested mortar mix is weak and friable over most of the 4 storey outer leaf walls above ground floor. As such, to eliminate the risk of progressive displacement and instability, the outer leaf of blockwork to Elevations 40-44 must be dismantled and replaced with a lightweight insulated cladding system. Due to the condition of the existing inner leaf, we have been advised this cladding cannot be fixed into the inner leaf blockwork but instead must span between the existing concrete columns. This will require the installation of secondary steelwork to support the new cladding rails.

Where the blockwork outer leaf is removed, secondary horizontal steelwork and non-combustible mineral wool insulation slabs are to be installed with a min 25mm continuous cavity between this and the new rainscreen cladding.

The total area of coverage required is 638.92sqm



| ELEVATION AREAS |                            |
|-----------------|----------------------------|
| Elevation 40    | 130.28m <sup>2</sup>       |
| Elevation 41    | 155.73m <sup>2</sup>       |
| Elevation 42    | 136.52m <sup>2</sup>       |
| Elevation 43    | 111.77m <sup>2</sup>       |
| Elevation 44    | 104.62m <sup>2</sup>       |
| <b>TOTAL</b>    | <b>638.92m<sup>2</sup></b> |

| EXTENT OF REPAIRS |   |
|-------------------|---|
|                   | Full Facade Replacement   |
|                   | Replace Lintels and Cills, Replace movement joints & render beads     |
|                   | Identify and Replace Areas of Bossed Render only                      |
|                   | Render removed, overcladding to cavity walls, replace lintels & cills |


## 4.1 Identified Repairs Elevations 38-39

In Mott MacDonald's condition report Elevations 38-39 are not showing the same signs of outward displacement, but water ingress is still an issue. Whilst the mortar to the outer leaf of these walls is considered adequate, repairs should be carried out to any defective lintels, cills, movement joints and render beads. The exact extent of these repairs still needs to be quantified, so for now two options have been highlighted.



Option 1 – retain the external render and carry out repairs as noted above.

Option 2 – carefully remove all external render, retain the outer leaf of blockwork and install a rainscreen cladding system to match Elevations 40-44 (minus new insulation slabs).



**The total area of coverage required is 147.61sqm**



Option 1



Option 2



| ELEVATION AREAS |                            |
|-----------------|----------------------------|
| Elevation 36    | 204.13m <sup>2</sup>       |
| Elevation 37    | 102.31m <sup>2</sup>       |
| <b>TOTAL</b>    | <b>306.44m<sup>2</sup></b> |
| Elevation 38    | 55.69m <sup>2</sup>        |
| Elevation 39    | 91.92m <sup>2</sup>        |
| <b>TOTAL</b>    | <b>147.61m<sup>2</sup></b> |

| EXTENT OF REPAIRS |   |
|-------------------|---|
|                   | Full Facade Replacement   |
|                   | Replace Lintels and Cills, Replace movement joints & render beads     |
|                   | Identify and Replace Areas of Bossed Render only                      |
|                   | Render removed, overcladding to cavity walls, replace lintels & cills |

## 4.1 Identified Repairs Elevations 36-37



In Mott MacDonald's condition report Elevations 36-37 are not affected by the water ingress issues highlighted elsewhere, nor is there any displacement or mortar concerns. As such it is proposed to identify any areas of bossed render which could present a hazard of falling onto the path below, carefully remove and replace with new.

**The total area of coverage required is 306.44sqm**

61419  
Gilbert Bain Hospital  
Elevation 36  
Level (m)  
A.O.D.



61419  
Gilbert Bain Hospital  
Elevation 37  
Level (m)  
A.O.D.



| ELEVATION AREAS |                            |
|-----------------|----------------------------|
| Elevation 36    | 204.13m <sup>2</sup>       |
| Elevation 37    | 102.31m <sup>2</sup>       |
| <b>TOTAL</b>    | <b>306.44m<sup>2</sup></b> |
| Elevation 38    | 55.69m <sup>2</sup>        |
| Elevation 39    | 91.92m <sup>2</sup>        |
| <b>TOTAL</b>    | <b>147.61m<sup>2</sup></b> |

| EXTENT OF REPAIRS |  |
|-------------------|--|
|                   | Full Facade Replacement  |
|                   | Replace Lintels and Cills,<br>Replace movement joints<br>& render beads        |
|                   | Identify and Replace<br>Areas of Bossed Render<br>only                         |
|                   | Render removed,<br>overcladding to cavity<br>walls, replace lintels &<br>cills |

## 4.2 Cladding Comparisons

Having identified the extent of cladding works to Elevations 36 to 44, Threesixty Architecture then carried out a comparison of several different types of cladding systems including aluminium rainscreen, anodised aluminium panels, fibre cement boards and mineral fibre insulated panels. Key factors in our consideration of each system focused on:

- Fire Rating
- Exposure Classification
- Fully certified specialist design and specification service
- Lead-in times
- Delivery timescales
- Colour Range

The table opposite summarises each cladding system and how it performs across each of these factors.

The only system which can achieve A1 combustible fire rating, a finish suitable for C5 exposure classification and a fully specialist contractor designed and certified system is the Valcan Vitradual Rainscreen Cladding system. Furthermore, lead-in times for both standard and non standard colours were more favourable with the Valcan system. Delivery timescales across all systems ranged from 2-4 weeks for Shetland. Whilst the area of new cladding required at the Gilbert Bain is over 630sqm (Option1) and potentially as much as 778sqm (Option 2) and therefore exceeding minimum order quantities for non-standard colours, Valcan was the only system that could provide standard colour range panels to site within 4-6 weeks.




In conclusion, this Stage 1 Report is based on the Valcan Vitradual system (from the 14 standard colour range) for costing and programme purposes.

| Cladding System          | Description  | Reference Image   | Finish applicable for C5 conditions | Leading Times In Weeks*  | Full System Certified/ accredited | Standard Colour Range                             | Pros/Cons  |
|--------------------------|--|---|-------------------------------------|--|-----------------------------------|---|--|
| Valcan Vitradual         | 3mm Aluminium Non-combustible A1-rated rainscreen façade panel |    | PVDF KYNAR 500 or FEVE              | Standard Colours: 1 to 2 weeks.<br>Non-standard Colours: 8 weeks.<br>Allow additional 2-4 weeks for delivery to Shetland | Yes                               | 14 Standard Colours in express range              | <b>Pros:</b> <ul style="list-style-type: none"> <li>• Full System. Incl. SER calculations and design</li> <li>• C5 as standard</li> <li>• Non-Combustible</li> <li>• Can be recycled at end of life</li> </ul> <b>Cons:</b>  |
| Taylor Maxwell Anvil     | 1.5 to 3mm Aluminium Panel A2 rated                            |   | Anodized                            | 8-10 Standard colours<br>Add 2 Weeks for delivery to Shetland  | Yes                               | 15 Standard Anodized Colours                      | <b>Pros:</b> <ul style="list-style-type: none"> <li>• Full System. Incl. SER calculations and design</li> <li>• Ease of installation</li> <li>• Non-Combustible</li> </ul> <b>Cons:</b> <ul style="list-style-type: none"> <li>• Risk of high Cost for anodizing for C5</li> </ul>   |
| Swiss Pearl Fibre Cement | A2 Fibre Cement Board  |  | Fibre-cement                        | 6-8 Weeks for standard colours, 8mm Panel<br>Add 2-4 Weeks for delivery to Shetland                                      | No                                | 9 to 5 Standard Colours Depending on panel finish | <b>Pros:</b> <ul style="list-style-type: none"> <li>• Ease of installation</li> <li>• Non-Combustible</li> <li>• Enhanced sound insulation</li> <li>• Made from recycled material</li> </ul> <b>Cons:</b> <ul style="list-style-type: none"> <li>• Not-Full system, third party manufacturer input required</li> </ul>   |
| Trimo Insulated Panel    | Mineral Fibre Insulated Panel                                  |  | Metal Composite Panel               | 7- 9 Week for standard product<br>Add 2 weeks for delivery to Shetland   | No                                | 11 Standard Colors                                | <b>Pros:</b> <ul style="list-style-type: none"> <li>• PVDF finish (recently completed in coastal conditions in Aberdeen without additional coating, varies from location to location)</li> <li>• Composite Panel including Insulation. Long warranties can be provided</li> <li>• Stackable self-supporting interlocking</li> <li>• Non-Combustible and provides fire rating up to 240 mins</li> </ul> <b>Cons:</b> <ul style="list-style-type: none"> <li>• Weight may be an issue onto existing</li> </ul> |

# 4.3 Cladding Typical Details Elevation 40-44

**Material Reference:**

1. 3mm Aluminium Cladding Cassette  
A1 Non-Combustible - Valcan Vitradual or equal - Secret fix, 15mm joints  
Finish: PVDF KYNAR 500 suitable for coastal location - Colour TBC
2. Proprietary Vertical Cladding Rails floor to floor span. Valcan Vitrafix system or equal to cladding sub-contractor design
3. Non-Combustible mineral wool insulation slabs. Rockwool rainscreen duoslab or equal to meet U-Value
4. 100mm Existing blockwork internal leaf wall to be retained.
5. Breather membrane
6. Existing concrete slab retained
7. Proprietary Valcar Vitrafix or equal cladding support channel, to be fixed to new horizontal steel member. Size TBC by cladding sub-contractor - Where applicable -Gap in-between insulation to be filled with non-combustible insulation to preserve thermal continuity.
8. min. 25mm Continuous vertical aerated cavity 60/60 min. Horizontal firestopping suitable for ventilated rainscreen, Rockwool OSB or equal, with intumescent expanding edge. Firestopping around openings, compartments and separation lines
9. New horizontal structural support, galvanised hot rolled to S.E design. Final position TBC. New horizontal structure to be fixed to existing columns to S.E design. Centres TBC. Thermal insulation from existing to be provided to avoid cold bridging
10. Aluminium flashing to match aluminium cladding. Finish: PVDF KYNAR 500 suitable for coastal location - Colour TBC
11. Existing/New lintel to be retained and made good to accommodate new windows
12. EPDM membrane overlap over breather membrane to cladding sub-contractor design
13. 60/60 FR Vertical full fill continuous rainscreen firestopping/cavity barrier at corners, around openings and at compartment lines. Max. cavity size 20 mt. Rockwool Firestop SP or equal
14. New UPVC Window, frame colour TBC. Windows to meet statutory U-Value as per table
15. Where possible, internal lining to be retained as per existing conditions, to be made good to accept new fenestration elements.
16. External leaf to be retained, render to be stripped, surface to be made good to accept new cladding
17. Existing block to be removed to allow for installation of new galv. structural outrigger to be fixed to existing concrete columns/walls
18. New cavity closer to be installed between existing masonry leaves upon removal of existing fenestration
19. Existing 200mm Concrete Wall retained, applicable to stair cores.
20. Cavity Tray/Weep Holes - Retention TBC - as part of the lintel replacing works






Indicative typical wall build-up details have been prepared for the two scenarios noted in Section 4.1 of this report, for high level costing purposes. These will be developed over the coming months through dialogue with the Structural Engineer and Valcan's specialist technical advisers.

## 4.3 Cladding Typical Details Elevation 38-39 (Option 2)

**Material Reference:**

1. 3mm Aluminium Cladding Cassette  
A1 Non-Combustible - Valcan Vitradual or equal - Secret fix, 15mm joints  
Finish: PVDF KYNAR 500 suitable for coastal location - Colour TBC
2. Proprietary Vertical Cladding Rails  
floor to floor span. Valcan Vitrafix system or equal to cladding sub-contractor design
3. Non-Combustible mineral wool insulation slabs. Rockwool rainscreen duoslab or equal to meet U-Value
4. 100mm Existing blockwork internal leaf wall to be retained.
5. Breather membrane
6. Existing concrete slab retained
7. Proprietary Valcan Vitrafix or equal cladding support channel, to be fixed to new horizontal steel member. Size TBC by cladding sub-contractor - Where applicable -Gap in-between insulation to be filled with non-combustible insulation to preserve thermal continuity.
8. min. 25mm Continuous vertical aerated cavity 60/60 min. Horizontal firestopping suitable for ventilated rainscreen, Rockwool OSB or equal, with intumescent expanding edge. Firestopping around openings, compartments and separation lines
9. New horizontal structural support, galvanised hot rolled to S.E design. Final position TBC. New horizontal structure to be fixed to existing columns to S.E design. Centres TBC. Thermal insulation from existing to be provided to avoid cold bridging
10. Aluminium flashing to match aluminium cladding. Finish: PVDF KYNAR 500 suitable for coastal location - Colour TBC
11. Existing/New lintel to be retained and made good to accommodate new windows
12. EPDM membrane overlap over breather membrane to cladding sub-contractor design
13. 60/60 FR Vertical full fill continuous rainscreen firestopping/cavity barrier at corners, around openings and at compartment lines. Max. cavity size 20 mt. Rockwool Firestop SP or equal
14. New UPVC Window, frame colour TBC. Windows to meet statutory U-Value as per table
15. Where possible, internal lining to be retained as per existing conditions, to be made good to accept new fenestration elements.
16. External leaf to be retained, render to be stripped, surface to be made good to accept new cladding
17. Existing block to be removed to allow for installation of new galv. structural outrigger to be fixed to existing concrete columns/walls
18. New cavity closer to be installed between existing masonry leafs upon removal of existing fenestration
19. Existing 200mm Concrete Wall retained, applicable to stair cores.
20. Cavity Tray/Weep Holes - Retention TBC - as part of the lintel replacing works




## 4.4 Structural Considerations

150 x 75 x 18 PFC Fixings to RC columns/walls 1no Hilti HIT HY200 HAS-U M16 with 125mm embedment. 300 x 90 x 41 PFC Fixings to RC columns 2no Hilti HIT HY200 HAS-U M20 with 170mm embedment. Intermediate fixings to blockwork outer leaf walls along channels Hilti HIT HY270 HAS-U M12 with 80mm embedment at 900mm centres.

**DRAFT**

Appendix A



150 x 75 x 18 PFC at 1.65m vertical centres between RC columns at south and west elevation

300 x 90 x 41 PFC at 1.65m vertical centres between RC columns at north elevation

150 x 75 x 18 PFC at 1.65m vertical centres between RC columns at east elevation

150 x 75 x 18 PFC at 1.65m vertical centres between RC columns and RC wall at south elevation

300 x 90 x 41 PFC at 1.65m vertical centres between RC columns at south elevation and at upper storey only at Lift/Stair No 9

In addition to the provision of their Report on Condition of External Façades dated December 2024, Mott MacDonald are in the process of carrying out the following further studies:

- Monitoring Plan for Facades
- Further Inspection of Facades 38/39
- Temporary internal propping of Facades 40-44

### Monitoring plan for facades

With the scaffold now in place around the Phase 1 elevations, it has been agreed that a monitoring plan needs to be implemented until such times that the outer leaves are dismantled, to ensure the integrity of the elevations doesn't deteriorate further during this time. Mott MacDonald will establish a baseline with a survey for cracking and walls out of plumb in April 2025. Visual inspections and checks of tell tales in the Plant Room would then be undertaken in June 2025 and on a three-monthly basis thereafter. They will be checking for any increase in cracking extent or widths; any increase in out of plumb measurements and any signs of bulging, in addition to movement in the tell tales. Furthermore, after any severe weather events of prolonged wind gusts greater than 70mph or reports of any significant water ingress the same monitoring inspections would be carried out at that time.

### Temporary strapping to Facades 40-44

To further protect the unstable facades from collapse during the works, the diagram opposite gives an indication of the potential external strapping Mott MacDonald proposes to install on the outer face of these elevations during the summer of 2025, the detail of which will be developed in the coming weeks.

### Further inspections of Facades 38/39

Following Robertson Group's site visit in late February, they queried whether the proposed work required to elevations 38 and 39 proposed in Mott MacDonald's Condition Report may need to be increased. As such, two options for these elevations are being considered. Option 1 will focus on remedial works only, to prevent water ingress based on retaining the existing external render finish with the provision of some new lintels, cills, movement joints and render stop beads. Option 2 assumes the extent of repairs is more extensive and would therefore benefit from the complete removal of the existing external render, making good the external block leaves to take a new rainscreen cladding system spanning between the reinforced columns with replacement of cills and lintels throughout.

Mott MacDonald carried out a more detailed inspection of these elevations on Friday 21st March and will produce a report confirming the number of lintels and cills that require to be replaced in due course. This will inform the decision on whether Option 1 or Option 2 is progressed.

### Temporary internal propping of Facades 40 – 44

Where the external blockwork leaves require to be dismantled, Internal propping to the inner leaf blockwork walls will be required for the period when the existing inner leaf alone is exposed to wind loading. Mott MacDonald are currently reviewing the strategy for this with Roberston Group and anticipate temporary wind posts should be installed at regular centres throughout the internal face of the inner leaves across elevations 40 – 44. These supports would remain in place for the duration of the cladding works, to be removed only when the façade replacements are complete. Mott MacDonald have produced draft drawings indicating likely positions and numbers of supports, however, further detailed consideration will be necessary as the design develops, to refine wind loadings for each elevation and for the interface with openings and support at the top storey steelwork.

The positions or all internal propping shall be coordinated with existing M&E services, such that modification to existing services is minimised as far as practicable in order to minimise operational disruption to the relevant departments.

Refer Mott MacDonald's drawings in Appendix 7.5 for details of the proposal to be developed

## 4.5 Mechanical & Electrical Considerations

This section provides a high level summary of the M&E services that are likely to be affected by the proposed installation of new external cladding. The following drawings identify the approximate location and type of M&E service which will interact with the removal of the existing outer blockwork leaf or installation of the new cladding, i.e. they will either connect to or pass through the building structure. All mechanical services are designated using an “M” reference, e.g. M1, M2, etc. All electrical services are designated using an “E” reference, e.g. E1, E2, etc.

| Drawing No.    | Drawing Description   |
|----------------|---|
| 790 (5-) ME200 | First Floor, Maternity & Renal Unit, M&E Service Penetrations |
| 790 (5-) ME400 | Third Floor, Plantroom, M&E Service Penetrations              |


The service references on the drawings correspond with the list of services below from the third floor to first floor level (highest M&E services to lowest).

| Reference | Floor Level        | Service Description                                      |
|-----------|--------------------|--|
| M1        | Third Floor        | AHU 10 Fresh air intake louvre                           |
| M2        | Third Floor        | AHU 1 & 2 Fresh Air Intake Louvre                        |
| M3        | Third Floor        | AHU 1 Exhaust Louvre                                     |
| M4        | Third Floor        | 20mm Flow & Return LTHW Pipes serving RCU AHU 1          |
| M5        | Third Floor        | AHU 2 Exhaust Louvre                                     |
| M6        | Third Floor        | AHU 2 Exhaust Louvre                                     |
| M7        | Third Floor        | Water Tank Room Exhaust Fan                              |
| M8        | Third Floor        | Water Tank Overflow Warning Pipes                        |
| E1        | Third Floor        | Lightning Protection tape (multiple locations)           |
| E2        | Third Floor        | TV Aerial Installation                                   |
| E3        | Third Floor        | Cable tray installation                                  |
| M9        | First Floor (Roof) | A/C Heat Pump Outdoor unit (Dental Store)                |
| M10       | First Floor (Roof) | A/C Heat Pump Outdoor unit (Dental Suite 1)              |
| M11       | First Floor (Roof) | A/C Heat Pump Outdoor unit (Dental Suite 2)              |
| M12       | First Floor (Roof) | A/C Heat Pump Outdoor unit (Maternity Ultrasound Room)   |
| M13       | First Floor (Roof) | A/C Heat Pump Outdoor unit (Renal Unit isolation room)   |
| M14       | First Floor (Roof) | A/C Heat Pump Outdoor unit (Maternity Bereavement Suite) |
| M15       | First Floor (Roof) | A/C Heat Pump Outdoor unit (Renal Unit)                  |
| E4        | First Floor (Roof) | Lightning Protection tape (multiple locations)           |
| E5        | First Floor (Roof) | TV Aerial Installation                                   |

For a more detailed assessment of the impact to the M&E services, please refer to separate Callidus Design preliminary report titled 'Proposed External Cladding Installation - Interface with M&E Services' Revision B dated 19th March 2025



**FIRST FLOOR: Maternity and Renal**



**THIRD FLOOR: Plantroom**

## 4.6 Advising Contractor Considerations

Robertson Construction was asked by Hub North, to join the team for this Stage 1 report, in order to impart their construction knowledge for such a complex project. They have been assisting NHS Shetland, Thomson Gray and the design team to develop proposals for the façade works at the Gilbert Bain Hospital focussing on programme, risk, buildability considerations, site logistics and estimating Prelims costs for the project. A site visit was undertaken on 18/02/25 to understand the site constraints and assess the impact of the proposed works on the live hospital.

**Delivery Considerations:** The impact of the façade works on the existing hospital accommodation was assessed and to ensure best continuity of clinical services, it has been concluded that the Maternity dept, Renal zone and Ward 3 will have to be fully vacated during the works. Rooms within these departments on Façade 36 could be used for non-patient functions during the construction period but will still be affected by noise and cold air, which limits the use of these spaces.

Furthermore, when removing the outer leaf of blockwork to facades 40-44, the existing cavity tray at the flat roof of the Outpatients Department has shown to be ineffective at stopping water entering the cavity and reaching the ground floor accommodation. Maintaining a fully functioning Outpatients department in its current location is critical for NHS Shetland during the works and reducing the risk of water ingress to the ground floor will be an important consideration as the works progress on site. The down takings methodology and replacement cladding sequence has been developed to minimise the risk of water ingress and is essential that some form of effective cavity tray/seal is installed as sections of the façade blockwork are removed. Suitable cavity tray products are being assessed and it is hoped a solution can be developed in the coming weeks. Water ingress at the ground floor Outpatients Dept. will remain a risk during severe weather and the effectiveness of the mitigation strategy will need to be carefully monitored during the works.

Whilst generally existing services equipment can be removed and relocated elsewhere during the recladding works and afterwards, the district heating pipes which run above the ground floor windows on Facades 36 and 37 make it impossible to address any render issues behind these services. It is currently unclear whether the render

behind these pipes is bossed, so for now the assumption has been made to retain the horizontal band of render behind the pipes and this will require further investigation at Stage 2.

Following inspection of the render on Façade 39, Robertson Construction believe it will all need to be removed. This has led to the inclusion of two options for Facades 38 and 39, and again, a decision on how these elevations are treated will be taken during Stage 2.

**Logistics:** The area of hospital car park (Location B) on the plan opposite has been identified for the contractor office, welfare and storage during the work. This zone will provide access to the façade workfaces via a temporary stair tower from car park level to the flat roof of the Outpatients Department. Any temporary accommodation required to maintain clinical services will need to be connected to the existing link corridor of the MRI suite. A timber framed, flat roofed, temporary corridor with hygienic internal finishes is proposed to serve as a suitable patient and staff route between the decanted spaces and the main GBH ground floor departments. A more detailed logistics plan can be found in the contractor's Summary report.

**Programme:** Robertson Construction have prepared a draft Construction Programme which is located in appendix 7.2 of this Stage 1 report. They have worked with Thomson Gray to agree the logic, sequence and durations identified to achieve a site start date in February 2026. As part of this exercise, they have liaised with a cladding subcontractor to understand the productivity outputs, weather risks and how the works can be sequenced to minimise water ingress.

The overall duration for the façade works has been assessed at 39 weeks, commencing 23/02/26 and completing 27/11/26. A further 11 weeks of activities have been identified to reinstate services, test and commission services, recommission clinical areas and remove the temporary accommodation. This gives a total contract duration of 52 weeks considering the Christmas 2026 2-week shutdown period.

For each façade there will be a two week 'winded off provision' to prepare it for the recladding works which can be split in sequence and timings as follows:

Elevation 44: 11 weeks from 06/03/26 – 30/04/26

Elevations 36 and 37: 7 weeks from 06/03/26 – 30/04/26

Elevation 42/part 43: 15 weeks from 20/04/26 – 04/08/26


Elevation 41: 12 weeks from 16/06/26 – 08/09/26

Elevation 40/part of 43: 12 weeks from 27/07/26 – 20/10/26

Elevation 39: Option 1 - 12 weeks from 24/08/26 – 17/11/26  
or Option 2 - 7 weeks from 25/08/26 – 14/10/26

Elevation 38: Option 1 - 6 weeks from 06/10/26 – 18/11/26  
or Option 2 - 6 weeks from 02/10/26 – 16/11/26

For a more detailed assessment of the logistics of the recladding element of the project, please refer to the separate Robertson Construction Summary Report to be read in conjunction with this Stage 1 document.





**5**

**Affected  
Areas**

## 5.0 Stakeholder Engagement

During this Stage 1 process, Stakeholder engagement has been vital to help crystallise the brief for potential decants, as well as ensuring decisions are fully collaborative. In addition to several Stakeholder workshops between Threesixty Architecture, NHS Shetland's Head of Estates, Project Clinical Lead and Senior Charge Midwife, the Head of Estates has also been holding initial stakeholder meetings with senior clinical staff in areas directly affected; including with Chief Nurse Acute Services, Assistant Director of Acute Services and Chief Midwife, Elective Care Lead, Senior Clinical Midwife, Senior Renal Staff Nurse. This helped refine essential and non-essential areas to allow build-up of the existing and proposed decant Schedules of Accommodation. High level discussions are also held at Hospital Management Team meetings and at the Area Medical Committee.

In addition, weekly meetings are held between SRO (Director of Acute Services) and Project Director. Biweekly meetings between SRO, Clinical Lead and Project Director. The project is a standing agenda item on Capital and Asset Management Group meetings and the Infection Control Committee meeting.




Image Caption: Maternity En Suite Room




Image Caption: Renal Dialysis Unit



Image Caption: Chemotherapy Treatment Room





Image Caption: Maternity Labour Suite



Image Caption: Ward 3



# 5.1 Maternity

Located on the first floor of the main hospital building, the Maternity Unit at Gilbert Bain provides facilities for outpatient assessments, two labour suites with paediatric resus, 4 en-suite single rooms and a dedicated Bereavement Suite, together with staff support spaces.

The department is served by two escape stairs and a lift with access to further circulation through the Renal Department and link corridor beyond.

During the Decant period the minimum accommodation to be provided would be outpatient assessment, one labour suite with paediatric resus, 2 en-suite single rooms and staff support services.

Due to staffing numbers, staff facilities must be retained alongside the clinical spaces.

### Options for Relocation

- Ronas
- Portacabins on site



### Existing Accommodation Schedule

24069A GBH Cladding Remedials

#### MATERNITY

| Room Type                   | No. | Area per room |  | Total Area SQM |           |
|-----------------------------|-----|---------------|--|----------------|-----------|
|                             |     | SQM           |  |                |           |
| Single Bedroom              | 4   | 13.15         |  | 52.6           | Clinical  |
| En-suite                    | 4   | 4.49          |  | 17.96          | Clinical  |
| Triage Room & En-suite      | 1   | 21.79         |  | 21.79          | Clinical  |
| Labour Room                 | 2   | 17.37         |  | 34.74          | Clinical  |
| Paediatric Resus            | 1   | 12.41         |  | 12.41          | Clinical  |
| Nurse Station               | 1   | 7.94          |  | 7.94           | Clinical  |
| Outpatients Consultant Room | 1   | 10.4          |  | 10.4           | Clinical  |
| Bereavement Suite           | 1   | 30.96         |  | 30.96          | Clinical  |
| <b>SUB-TOTAL</b>            |     |               |  |                |           |
| Disposal Room               | 1   | 8.94          |  | 8.94           | Ancillary |
| Sluice/Test                 | 1   | 6.84          |  | 6.84           | Ancillary |
| Labour Sluice/Test          | 1   | 2.53          |  | 2.53           | Ancillary |
| Store                       | 4   | 3.38          |  | 13.51          | Ancillary |
| Clinical Store              | 1   | 9.39          |  | 9.39           | Ancillary |
| Shower Room                 | 2   | 7.18          |  | 14.36          | Ancillary |
| <b>SUB-TOTAL</b>            |     |               |  |                |           |
| Staff Change & WC           | 1   | 10.07         |  | 10.07          | Staff     |
| Office                      | 3   | 9.66          |  | 28.97          | Staff     |
| Staff Room/Pantry           | 1   | 16.42         |  | 16.42          | Staff     |
| <b>SUB-TOTAL</b>            |     |               |  |                |           |
| <b>SUB-TOTAL</b>            |     |               |  | <b>55.46</b>   |           |
| <b>TOTAL</b>                |     |               |  | <b>299.83</b>  |           |
| Circulation/Plant           |     |               |  | 158.41         |           |
| <b>GRAND TOTAL</b>          |     |               |  | <b>458.24</b>  |           |

### Essential Accommodation Schedule

Department Decants

24069A GBH Cladding Remedials

Department Decants

#### MATERNITY

| Room Type                       | No. | Area per room |  | Total Area SQM |           |
|---------------------------------|-----|---------------|--|----------------|-----------|
|                                 |     | SQM           |  |                |           |
| Single Bedroom                  | 2   | 13.15         |  | 26.3           | Clinical  |
| En-suite                        | 2   | 4.85          |  | 9.7            | Clinical  |
| Triage Room & En-suite          | 1   | 21.79         |  | 21.79          | Clinical  |
| Labour Room                     | 1   | 17.37         |  | 17.37          | Clinical  |
| Paediatric Resus                | 1   | 12.41         |  | 12.41          | Clinical  |
| Nurse Station                   | 1   | 7.94          |  | 7.94           | Clinical  |
| Outpatients Consultant Room     | 1   | 10.4          |  | 10.4           | Clinical  |
| <b>SUB TOTAL</b>                |     |               |  | <b>105.91</b>  |           |
| Disposal Room                   | 1   | 8.94          |  | 8.94           | Ancillary |
| Sluice/Test                     | 1   | 6.84          |  | 6.84           | Ancillary |
| Store                           | 2   | 3.38          |  | 6.76           | Ancillary |
| Clinical Store                  | 1   | 9.39          |  | 9.39           | Ancillary |
| Shower Room                     | 1   | 7.18          |  | 7.18           | Ancillary |
| <b>SUB TOTAL</b>                |     |               |  | <b>39.11</b>   |           |
| Staff Change & WC               | 1   | 9.63          |  | 9.63           | Staff     |
| Office                          | 2   | 9.66          |  | 19.32          | Staff     |
| Staff Room/Pantry               | 1   | 16.42         |  | 16.42          | Staff     |
| <b>SUB TOTAL</b>                |     |               |  | <b>45.37</b>   |           |
| <b>TOTAL</b>                    |     |               |  | <b>190.39</b>  |           |
| Circulation/Plant Allowance 30% |     |               |  | 57.12          |           |
| <b>GRAND TOTAL</b>              |     |               |  | <b>247.507</b> |           |

Total Area for Decant : **247.507m<sup>2</sup>**



# 5.2 Renal

The Renal Department provides dialysis to day patients 3 times per week and is situated on the first floor of the main hospital sandwiched between maternity and the link corridor.

The current space has 7 standard dialysis bays plus an isolation bay and staff support services which must be relocated alongside the clinical space.

During the decant and assuming sessions can be reorganised in half day periods a minimum of 4 standard bays plus an isolation bay are required.

### Options for Relocation

- Ronas
- Portacabins on site
- Portable Vehicle within the hospital grounds



### Existing Accommodation Schedule

24069A GBH Cladding Remedials

#### RENAL

| Room Type           | No. | Area per room |                | Clinical  |
|---------------------|-----|---------------|----------------|-----------|
|                     |     | SQM           | Total Area SQM |           |
| Renal Dialysis Bay  | 7   | 7.22          | 50.55          | Clinical  |
| Staff Base          | 1   | 8.8           | 8.8            | Clinical  |
| Isolation Renal Bay | 1   | 8.7           | 8.7            | Clinical  |
| <b>SUB-TOTAL</b>    |     |               | <b>68.05</b>   |           |
| Sluice Room         | 1   | 3.59          | 3.59           | Ancillary |
| Dis. WC             | 1   | 4.86          | 4.86           | Ancillary |
| Staff WC            | 1   | 3.59          | 3.59           | Ancillary |
| Renal Store         | 1   | 12.45         | 12.45          | Ancillary |
| DSR                 | 1   | 4.86          | 4.86           | Ancillary |
| <b>SUB-TOTAL</b>    |     |               | <b>29.35</b>   |           |
| Renal Office        | 1   | 12.45         | 12.45          | Staff     |
| <b>SUB-TOTAL</b>    |     |               | <b>12.45</b>   |           |
| <b>TOTAL</b>        |     |               | <b>109.85</b>  |           |
| Circulation/Plant   |     |               | 45.42          |           |
| <b>GRAND TOTAL</b>  |     |               | <b>155.27</b>  |           |

### Essential Accommodation Schedule

Department Decants

24069A GBH Cladding Remedials

Department Decants

#### RENAL

| Room Type                       | No. | Area per room |                | Clinical  |
|---------------------------------|-----|---------------|----------------|-----------|
|                                 |     | SQM           | Total Area SQM |           |
| Renal Dialysis Bay              | 4   | 7.22          | 28.88          | Clinical  |
| Staff Base                      | 1   | 8.8           | 8.8            | Clinical  |
| Isolation Renal Bay             | 1   | 8.7           | 8.7            | Clinical  |
| <b>SUB TOTAL</b>                |     |               | <b>46.38</b>   |           |
| Sluice Room                     | 1   | 3.59          | 3.59           | Ancillary |
| Dis. WC                         | 1   | 4.86          | 4.86           | Ancillary |
| Renal Store                     | 1   | 12.45         | 12.45          | Ancillary |
| DSR                             | 1   | 4.86          | 4.86           | Ancillary |
| <b>SUB TOTAL</b>                |     |               | <b>25.76</b>   |           |
| Renal Office                    | 1   | 12.45         | 12.45          | Staff     |
| <b>SUB TOTAL</b>                |     |               | <b>12.45</b>   |           |
| <b>TOTAL</b>                    |     |               | <b>84.59</b>   |           |
| Circulation/Plant Allowance 30% |     |               | 25.38          |           |
| <b>GRAND TOTAL</b>              |     |               | <b>109.967</b> |           |

Total Area for Decant : **109.967m<sup>2</sup>**



# 5.3 Ward 3

Ward 3 is located on the second floor of the hospital and provides 21 beds in a mix of room types. These include 6 no single en-suite rooms, 3 no. four bed wards and a 3 bed isolation bay. Staff support areas are located off the main ward within the Stair 9 tower.

Ward 3 is served by 3no escape stairs with 1no lift and access to the 2nd lift via the link corridor.

Initially 2 options were considered for Ward 3.

Option 1: the minimum provision of 16 beds which assumed the 7 overflow beds could be made available in Ward 1 (with alterations made to sanitary facilities).


Option 2: the maximum provision of 21 beds leaving Ward 1 untouched.

In both options the bed types had to include a minimum of 6 no en-suite single rooms and an isolation facility.

Through further discussion with the Client team, and given that Ward 1's empty beds are used for surge capacity which is often close to full, it was agreed that only Option 2 is viable for decant options.

### Options for Relocation

- Ronas
- Portacabins on site (staff facilities could be on a first floor directly above the ward area).



### Existing Accommodation Schedule

24069A GBH Cladding Remedials

#### WARD 3

| Room Type              | No. | Area per room |                | Function  | Totals        |
|------------------------|-----|---------------|----------------|-----------|---------------|
|                        |     | SQM           | Total Area SQM |           |               |
| Single Bedroom         | 6   | 12.08         | 72.5           | Clinical  |               |
| 3 Bed Isolation Bay    | 1   | 37.25         | 37.25          | Clinical  |               |
| 4 Bed Room             | 3   | 39.24         | 117.72         | Clinical  |               |
| En-Suite               | 10  | 4.19          | 41.9           | Clinical  |               |
| Nurse Station          | 2   | 7.4           | 14.8           | Clinical  |               |
| <b>SUB-TOTAL</b>       |     |               |                |           | <b>284.17</b> |
| Linen Store            | 1   | 10            | 10             | Ancillary |               |
| Store                  | 1   | 11.22         | 11.22          | Ancillary |               |
| Staff WC               | 1   | 2.18          | 2.18           | Ancillary |               |
| D.S.R                  | 1   | 8.45          | 8.45           | Ancillary |               |
| Dirty Utility          | 1   | 20.66         | 20.66          | Ancillary |               |
| Preparation Room       | 1   | 16.29         | 16.29          | Ancillary |               |
| <b>SUB-TOTAL</b>       |     |               |                |           | <b>68.8</b>   |
| Ward Nurses Office     | 1   | 10.74         | 10.74          | Staff     |               |
| Pantry                 | 1   | 9.53          | 9.53           | Staff     |               |
| Staff Room             | 1   | 11.35         | 11.35          | Staff     |               |
| Multi Disiplinary Room | 1   | 13.87         | 13.87          | Staff     |               |
| Doctor's Room          | 1   | 17.04         | 17.04          | Staff     |               |
| SCN Office             | 1   | 9.94          | 9.94           | Staff     |               |
| <b>SUB-TOTAL</b>       |     |               |                |           | <b>72.47</b>  |
| <b>TOTAL</b>           |     |               |                |           | <b>425.44</b> |
| Circulation/Plant      |     |               |                |           | 185.92        |
| <b>GRAND TOTAL</b>     |     |               |                |           | <b>611.36</b> |

### Essential Accommodation Schedule

Department Decants


24069A GBH Cladding Remedials

Department Decants

#### WARD 3

| Room Type                       | No. | Area per room |                | Function  | Totals         |
|---------------------------------|-----|---------------|----------------|-----------|----------------|
|                                 |     | SQM           | Total Area SQM |           |                |
| Single Bedroom                  | 6   | 12.08         | 72.48          | Clinical  |                |
| 3 Bed Isolation Bay             | 1   | 37.25         | 37.25          | Clinical  |                |
| 4 Bed Room                      | 3   | 39.24         | 117.72         | Clinical  |                |
| En-Suite                        | 10  | 4.19          | 41.9           | Clinical  |                |
| Nurse Station                   | 2   | 7.4           | 14.8           | Clinical  |                |
| <b>SUB TOTAL</b>                |     |               |                |           | <b>284.15</b>  |
| Linen Store                     | 1   | 10            | 10             | Ancillary |                |
| Store                           | 1   | 11.22         | 11.22          | Ancillary |                |
| Staff WC                        | 1   | 2.18          | 2.18           | Ancillary |                |
| D.S.R                           | 1   | 8.45          | 8.45           | Ancillary |                |
| Dirty Utility                   | 1   | 20.66         | 20.66          | Ancillary |                |
| Preparation Room                | 1   | 16.29         | 16.29          | Ancillary |                |
| <b>SUB TOTAL</b>                |     |               |                |           | <b>68.8</b>    |
| Pantry                          | 1   | 9.53          | 9.53           | Staff     |                |
| Staff Room                      | 1   | 11.35         | 11.35          | Staff     |                |
| Nurses/Doctors Office           | 1   | 20            | 20             | Staff     |                |
| SCN Office                      | 1   | 9.94          | 9.94           | Staff     |                |
| <b>SUB TOTAL</b>                |     |               |                |           | <b>50.82</b>   |
| <b>TOTAL</b>                    |     |               |                |           | <b>403.77</b>  |
| Circulation/Plant Allowance 30% |     |               |                |           | 121.13         |
| <b>GRAND TOTAL</b>              |     |               |                |           | <b>524.901</b> |

Total Area for Decant : **524.901m<sup>2</sup>**



# 5.4 Clinical Skills

The facilities in the old Ronas ward on the second floor are not directly impacted by the facade replacement works, but have been identified as able to be relocated to make way for decanted accommodation better suited to remain within the hospital envelope, in close proximity to identified co-dependant hospital departments (Such as X-ray, theatre etc).


The main part of the space provides training rooms for Clinical Skills as well as the Junior Doctors Office and the single largest meeting room on the hospital grounds.

Some of the spaces are not currently used (Endoscopy, Various shower rooms) and other spaces are shared with the Chemo Department directly next door.

The minimum provision of any decant would need to provide the meeting room, Junior Doctors Office (which could be located separate from clinical skills), the Sim/Observation Room, a 4 bay clinical skills room plus two additional side bays. Other staff facilities could be shared with other departments.

### Options for Relocation

- Meeting Room to SDEC
- Junior Doctors Office + Male Changing to the north side of Ward 3
- Clinical Skills Department to a First Floor Portacabin on site
- Full Department to first floor portacabins on site.



### Existing Accommodation Schedule

24069A GBH Cladding Remedials

#### CLINICAL SKILLS

| Room Type                       | No. | Area per room |  | Total Area SQM |           |
|---------------------------------|-----|---------------|--|----------------|-----------|
|                                 |     | SQM           |  |                |           |
| Clinical Skills Room            | 1   | 56.4          |  | 56.4           | Clinical  |
| Sim Room with Observation Space | 1   | 25.54         |  | 25.54          | Clinical  |
| Endoscopy Room                  | 1   | 34.44         |  | 34.44          | Clinical  |
| <b>SUB-TOTAL</b>                |     |               |  | <b>116.38</b>  |           |
| Bariatric Store Room            | 1   | 11.76         |  | 11.76          | Ancillary |
| Bath/Shower/WC                  | 1   | 12.59         |  | 12.59          | Ancillary |
| WC                              | 2   | 6.13          |  | 12.26          | Ancillary |
| Staff Kitchen                   | 1   | 6.26          |  | 6.26           | Ancillary |
| Store                           | 3   | 2.82          |  | 8.46           | Ancillary |
| <b>SUB-TOTAL</b>                |     |               |  | <b>51.33</b>   |           |
| Junior Doctors Office           | 1   | 23.8          |  | 23.8           | Staff     |
| Clinical Education Office       | 1   | 8.48          |  | 8.48           | Staff     |
| Meeting Room                    | 1   | 33.45         |  | 33.45          | Staff     |
| <b>SUB-TOTAL</b>                |     |               |  | <b>65.73</b>   |           |
| <b>TOTAL</b>                    |     |               |  | <b>233.44</b>  |           |
| Circulation/Plant               |     |               |  | 70.03          |           |
| <b>GRAND TOTAL</b>              |     |               |  | <b>303.47</b>  |           |

### Essential Accommodation Schedule

24069A GBH Cladding Remedials


#### CLINICAL SKILLS

| Room Type                       | No. | Area per room |  | Total Area SQM |           |
|---------------------------------|-----|---------------|--|----------------|-----------|
|                                 |     | SQM           |  |                |           |
| Clinical Skills Room            | 1   | 56.4          |  | 56.4           | Clinical  |
| Sim Room with Observation Space | 1   | 25.54         |  | 25.54          | Clinical  |
| Clinical Skills Bay             | 2   | 14            |  | 28             | Clinical  |
| <b>SUB-TOTAL</b>                |     |               |  | <b>109.94</b>  |           |
| WC                              | 2   | 6.13          |  | 12.26          | Ancillary |
| Staff Kitchen                   | 1   | 6.26          |  | 6.26           | Ancillary |
| DSR                             | 1   | 3             |  | 3              | Ancillary |
| Disposal / Sluice               | 1   | 12            |  | 12             | Ancillary |
| Store                           | 3   | 2.82          |  | 8.46           | Ancillary |
| <b>SUB-TOTAL</b>                |     |               |  | <b>41.98</b>   |           |
| Clinical Education Office       | 1   | 8.48          |  | 8.48           | Staff     |
| <b>SUB-TOTAL</b>                |     |               |  | <b>8.48</b>    |           |
| <b>TOTAL</b>                    |     |               |  | <b>160.4</b>   |           |
| Circulation/Plant Allowance 30% |     |               |  | 48.12          |           |
| <b>GRAND TOTAL</b>              |     |               |  | <b>208.52</b>  |           |

#### To be provided elsewhere in Hospital

|                       |   |       |  |              |       |
|-----------------------|---|-------|--|--------------|-------|
| Junior Doctors Office | 1 | 23.8  |  | 23.8         | Staff |
| Meeting Room          | 1 | 33.45 |  | 33.45        | Staff |
| <b>SUB-TOTAL</b>      |   |       |  | <b>57.25</b> |       |

Total Area for Decant : **208.52m<sup>2</sup>**



# 5.5 Chemo

Chemo is situated in the old Ronas Ward on the second floor of the main hospital building, alongside the Clinical Skills wing.


The 3 existing Chemo Bays are in the process of being expanded to 5-6 bays in the old Chemo Office, which is now located elsewhere in the building.

With the increase in Paediatric Chemo and also generally, any decanted facility will need to provide 2 separate spaces each with 3 bays and a patient toilet to maximise treatment options.

It could be relocated anywhere on the hospital grounds but must have it's own private waiting room and be kept away from any infection / isolation spaces.

### Options for Relocation

- Portacabins on Site
- Portable Vehicle within hospital grounds



### Existing Accommodation Schedule

|                                      |     | Area per room |                |           |               |
|--------------------------------------|-----|---------------|----------------|-----------|---------------|
| Room Type                            | No. | SQM           | Total Area SQM |           |               |
| 24069A GBH Cladding Remedials        |     |               |                |           |               |
| CHEMO                                |     |               |                |           |               |
| Nurse Station                        | 1   | 8.26          | 8.26           | Clinical  |               |
| Chemotherapy Treatment Room (3 Bays) | 1   | 35.85         | 35.85          | Clinical  |               |
| Chemotherapy Treatment Room (3 Bays) | 1   | 30.2          | 30.2           | Clinical  |               |
| <b>SUB-TOTAL</b>                     |     |               |                |           | <b>74.31</b>  |
| Ensuite                              | 3   | 4.79          | 14.37          | Ancillary |               |
| Chemotherapy Waiting Room            | 1   | 14.67         | 14.67          | Ancillary |               |
| Staff WC                             | 1   | 6.29          | 6.29           | Ancillary |               |
| Disposal/Sluice                      | 1   | 12.36         | 12.36          | Ancillary |               |
| Panty                                | 1   | 7.2           | 7.2            | Ancillary |               |
| DSR                                  | 1   | 5.05          | 5.05           | Ancillary |               |
| Store                                | 2   | 2.04          | 4.08           | Ancillary |               |
| <b>SUB-TOTAL</b>                     |     |               |                |           | <b>64.02</b>  |
| Video Conferencing                   | 1   | 9.79          | 9.79           | Staff     |               |
| <b>SUB-TOTAL</b>                     |     |               |                |           | <b>9.79</b>   |
| <b>TOTAL</b>                         |     |               |                |           | <b>148.12</b> |
| Circulation/Plant                    |     |               |                |           | 28.51         |
| <b>GRAND TOTAL</b>                   |     |               |                |           | <b>176.63</b> |

### Essential Accommodation Schedule

|                                      |     | Area per room |                |           |               |
|--------------------------------------|-----|---------------|----------------|-----------|---------------|
| Room Type                            | No. | SQM           | Total Area SQM |           |               |
| 24069A GBH Cladding Remedials        |     |               |                |           |               |
| CHEMO                                |     |               |                |           |               |
| Nurse Station                        | 1   | 8.26          | 8.26           | Clinical  |               |
| Chemotherapy Treatment Room (3 Bays) | 1   | 35.85         | 35.85          | Clinical  |               |
| Chemotherapy Treatment Room (3 Bays) | 1   | 30.2          | 30.2           | Clinical  |               |
| <b>SUB-TOTAL</b>                     |     |               |                |           | <b>74.31</b>  |
| Ensuite                              | 3   | 4.79          | 14.37          | Ancillary |               |
| Chemotherapy Waiting Room            | 1   | 14.67         | 14.67          | Ancillary |               |
| Staff WC                             | 1   | 6.29          | 6.29           | Ancillary |               |
| Disposal/Sluice                      | 1   | 12.36         | 12.36          | Ancillary |               |
| Panty                                | 1   | 7.2           | 7.2            | Ancillary |               |
| DSR                                  | 1   | 5.05          | 5.05           | Ancillary |               |
| Store                                | 2   | 2.04          | 4.08           | Ancillary |               |
| <b>SUB-TOTAL</b>                     |     |               |                |           | <b>64.02</b>  |
| Video Conferencing                   | 1   | 9.79          | 9.79           | Staff     |               |
| <b>SUB-TOTAL</b>                     |     |               |                |           | <b>9.79</b>   |
| <b>TOTAL</b>                         |     |               |                |           | <b>148.12</b> |
| Circulation/Plant Allowance 30%      |     |               |                |           | 44.44         |
| <b>GRAND TOTAL</b>                   |     |               |                |           | <b>192.56</b> |

Total Area for Decant : **192.56m<sup>2</sup>**



# 5.6 Outpatients

Located on the ground floor, outpatients wraps around the Stair 9 core and Dental which sits within the original base of the upper floors of the 4 storey tower requiring facade replacement.

Temporary propping has been installed throughout the department, to support the scaffold to façades built off the outpatients roof.


Whilst it is now operational again, there are concerns that when the façades are removed, water ingress may increase, necessitating outpatients to be temporarily decanted for the duration of the works.

If so, it will need to be relocated in it's entirety.

It may be possible to lose 2 clinical rooms over to Lerwick Health Centre but this can't be confirmed at this stage.

### Options for Relocation

- Full department to portacabins on hospital grounds
- Dental reception to be relocated to Main Hospital Reception



### Existing Accommodation Schedule

24069A GBH Cladding Remedials

#### OUTPATIENTS

| Room Type                             | No. | Area per room |        | Total Area SQM | Clinical      |
|---------------------------------------|-----|---------------|--------|----------------|---------------|
|                                       |     | SQM           | SQM    |                |               |
| Consulting Room                       | 8   | 16.49         | 131.92 | 131.92         | Clinical      |
| Test Room                             | 1   | 10.02         | 10.02  | 10.02          | Clinical      |
| Pre Assess Room                       | 2   | 16.45         | 32.9   | 32.9           | Clinical      |
| Nurse Treatment Room                  | 1   | 14.51         | 14.51  | 14.51          | Clinical      |
| Eye Injection Room                    | 1   | 16.81         | 16.81  | 16.81          | Clinical      |
| Laser Room                            | 1   | 16            | 16     | 16             | Clinical      |
| Nurses Rm/Store/Minor Procedures      | 1   | 18.4          | 18.4   | 18.4           | Clinical      |
| Phototherapy                          | 1   | 26.19         | 26.19  | 26.19          | Clinical      |
| <b>SUB-TOTAL</b>                      |     |               |        |                | <b>266.75</b> |
| Servers                               | 1   | 4.1           | 4.1    | 4.1            | Ancillary     |
| Nurse Store                           | 1   | 4.61          | 4.61   | 4.61           | Ancillary     |
| Dis WC                                | 1   | 3.3           | 3.3    | 3.3            | Ancillary     |
| Unisex Acc WC                         | 1   | 6.46          | 6.46   | 6.46           | Ancillary     |
| Waiting Area (serves 14 Clinical rms) | 1   | 51.65         | 51.65  | 51.65          | Ancillary     |
| DSR                                   | 1   | 3.12          | 3.12   | 3.12           | Ancillary     |
| <b>SUB-TOTAL</b>                      |     |               |        |                | <b>73.24</b>  |
| Reception (Serves OP & Dental)        | 1   | 15.95         | 15.95  | 15.95          | Staff         |
| Staff Base                            | 1   | 5.79          | 5.79   | 5.79           | Staff         |
| Staff WC                              | 1   | 2.88          | 2.88   | 2.88           | Staff         |
| Staff Kitchen                         | 1   | 5.52          | 5.52   | 5.52           | Staff         |
| Office                                | 1   | 9.11          | 9.11   | 9.11           | Staff         |
| <b>SUB-TOTAL</b>                      |     |               |        |                | <b>39.25</b>  |
| <b>TOTAL</b>                          |     |               |        |                | <b>379.24</b> |
| Circulation/Plant                     |     |               |        | 142.43         |               |
| <b>GRAND TOTAL</b>                    |     |               |        |                | <b>521.67</b> |

Department Decants

### Essential Accommodation Schedule


24069A GBH Cladding Remedials

#### OUTPATIENTS

| Room Type                             | No. | Area per room |       | Total Area SQM | Clinical       |
|---------------------------------------|-----|---------------|-------|----------------|----------------|
|                                       |     | SQM           | SQM   |                |                |
| Consulting Room                       | 8   | 14            | 112   | 112            | Clinical       |
| Test Room                             | 1   | 10.02         | 10.02 | 10.02          | Clinical       |
| Pre Assess Room                       | 2   | 14            | 28    | 28             | Clinical       |
| Nurse Treatment Room                  | 1   | 14.51         | 14.51 | 14.51          | Clinical       |
| Eye Injection Room                    | 1   | 16.81         | 16.81 | 16.81          | Clinical       |
| Laser Room                            | 1   | 16            | 16    | 16             | Clinical       |
| Nurses Rm/Store/Minor Procedures      | 1   | 18.4          | 18.4  | 18.4           | Clinical       |
| Phototherapy                          | 1   | 14            | 14    | 14             | Clinical       |
| <b>SUB-TOTAL</b>                      |     |               |       |                | <b>229.74</b>  |
| Nurse Store                           | 1   | 4.61          | 4.61  | 4.61           | Ancillary      |
| Dis WC                                | 1   | 3.3           | 3.3   | 3.3            | Ancillary      |
| Unisex Acc WC                         | 1   | 6.46          | 6.46  | 6.46           | Ancillary      |
| Waiting Area (serves 12 Clinical rms) | 1   | 50            | 50    | 50             | Ancillary      |
| DSR                                   | 1   | 3.12          | 3.12  | 3.12           | Ancillary      |
| <b>SUB-TOTAL</b>                      |     |               |       |                | <b>67.49</b>   |
| Reception (Serves OP only)            | 1   | 12            | 12    | 12             | Staff          |
| Staff Base                            | 1   | 5.79          | 5.79  | 5.79           | Staff          |
| Staff WC                              | 1   | 2.88          | 2.88  | 2.88           | Staff          |
| Staff Kitchen                         | 1   | 5.52          | 5.52  | 5.52           | Staff          |
| Office                                | 1   | 9.11          | 9.11  | 9.11           | Staff          |
| <b>SUB-TOTAL</b>                      |     |               |       |                | <b>35.3</b>    |
| <b>TOTAL</b>                          |     |               |       |                | <b>332.53</b>  |
| Circulation/Plant Allowance 30%       |     |               |       | 99.76          |                |
| <b>GRAND TOTAL</b>                    |     |               |       |                | <b>432.289</b> |

Department Decants

**Total Area for Decant : 432.289m<sup>2</sup>**




# 5.7 ECG

ECG is located on the ground floor of the main building, in-between Dental and CT Scanning. It's position sits directly below the outside face of Renal and ward 3 therefore similarly to outpatients, should water ingress become a problem during the facade works, it may need to be temporarily decanted in it's entirety.

Due to co-location dependencies, the decant facility would suit being sited alongside Ward 3.

### Options for Relocation

- SDEC (Which would not require to be re-provided elsewhere)
- Alongside the decanted Ward 3 in Portacabins in hospital grounds



### Existing Accommodation Schedule

24069A GBH Cladding Remedials

| Room Type          | No. | Area per room |  | Total Area SQM | Category  | Sub-TOTAL    |
|--------------------|-----|---------------|--|----------------|-----------|--------------|
|                    |     | SQM           |  |                |           |              |
| E.T.T Room         | 1   | 19.8          |  | 19.8           | Clinical  |              |
| E.C.G & Audio Room | 1   | 15.78         |  | 15.78          | Clinical  |              |
| <b>SUB-TOTAL</b>   |     |               |  |                |           | <b>35.58</b> |
| Waiting Room       | 1   | 6.45          |  | 6.45           | Ancillary |              |
| Store              | 1   | 6.13          |  | 6.13           | Ancillary |              |
| <b>SUB-TOTAL</b>   |     |               |  |                |           | <b>12.58</b> |
| Office             | 1   | 9.19          |  | 9.19           | Staff     |              |
| <b>SUB-TOTAL</b>   |     |               |  |                |           | <b>9.19</b>  |
| <b>TOTAL</b>       |     |               |  |                |           | <b>57.35</b> |
| Circulation/Plant  |     |               |  |                |           | 2.13         |
| <b>GRAND TOTAL</b> |     |               |  |                |           | <b>59.48</b> |

Department Decants

### Essential Accommodation Schedule

24069A GBH Cladding Remedials

| Room Type                       | No. | Area per room |  | Total Area SQM | Category  | Sub-TOTAL    |
|---------------------------------|-----|---------------|--|----------------|-----------|--------------|
|                                 |     | SQM           |  |                |           |              |
| E.T.T Room                      | 1   | 19.8          |  | 19.8           | Clinical  |              |
| E.C.G & Audio Room              | 1   | 15.78         |  | 15.78          | Clinical  |              |
| <b>SUB-TOTAL</b>                |     |               |  |                |           | <b>35.58</b> |
| Waiting Room                    | 1   | 6.45          |  | 6.45           | Ancillary |              |
| Store                           | 1   | 6.13          |  | 6.13           | Ancillary |              |
| <b>SUB-TOTAL</b>                |     |               |  |                |           | <b>12.58</b> |
| Office                          | 1   | 9.19          |  | 9.19           | Staff     |              |
| <b>SUB-TOTAL</b>                |     |               |  |                |           | <b>9.19</b>  |
| <b>TOTAL</b>                    |     |               |  |                |           | <b>57.35</b> |
| Circulation/Plant Allowance 30% |     |               |  |                |           | 17.21        |
| <b>GRAND TOTAL</b>              |     |               |  |                |           | <b>74.56</b> |

Department Decants

Total Area for Decant : **74.56m<sup>2</sup>**



6

Decant  
Options

## 6.1 Department Decants Maternity Decant Options [247.507m<sup>2</sup>]


Two options were identified for the decant of a reduced Maternity Department.

Option 1 considered relocation within the main hospital building, to the 2nd floor ex Ronas Ward area currently being used for Clinical Skills Training. This option would ensure that Maternity Services remain close to other key departments such as Ultrasound and Theatres, which are critical for emergency care.

Option 2 considered relocation to temporary modular accommodation within the car park of the hospital, potentially with a covered link connecting into the main hospital building.

With Chemotherapy able to remain alongside minimal alterations required to accommodate Maternity within Ronas, and maintaining Maternity's closer proximity to the Theatres for emergency procedures, **Option 1** is deemed the preferred decant solution.

### OPTION 1: Maternity into Ronas Ward



Total Required Area in Ronas Ward  
247.507m<sup>2</sup>

### OPTION 2: Maternity into Portacabins



10no. 7540x3460mm Portacabins  
260.884m<sup>2</sup>

## 6.1 Department Decants

### Renal Decant Options [109.967m<sup>2</sup>]

Three options were identified for the decant of the Renal Department.


Option 1 considered relocation within the main hospital building, to the 2nd floor ex Ronas Ward area currently being used for Clinical Skills Training. This option could consolidate regular outpatient procedures alongside Chemotherapy.

Option 2 considered relocation to temporary modular accommodation within the car park of the hospital.

Option 3 considered relocation to a Mobile Dialysis Unit within the car park of the hospital.

Relocating Renal to Ronas (either alongside Chemo or by itself) would leave too little usable residual space in Ronas to be assigned to another decanted department. With space at a premium within the car park decant zone, **Option 3** is deemed the preferred decant solution, as a Mobile Dialysis Unit for up to 5 chairs is available and takes up less space in the car park.

#### OPTION 1: Renal into Ronas Ward



Total Required Area in Ronas Ward  
109.967m<sup>2</sup>

#### OPTION 2: Renal into Portacabins



4no. 9940x3460mm  
Portacabins  
137.57m<sup>2</sup>

#### OPTION 3: Renal into Mobile Units



13800x4490mm  
5 Bay Infusion  
Mobile Unit  
55.6m<sup>2</sup>

## 6.1 Department Decants Ward 3 Decant Options [524.901m<sup>2</sup>]



Two options were identified for the decant of the full 21 bed General Medical Ward 3.

Option 1 considered relocation within the main hospital building, to the 2nd floor ex Ronas Ward area currently being used for Clinical Skills Training and Chemotherapy.

Option 2 considered relocation to temporary modular accommodation within the car park of the hospital, potentially with a covered link connecting into the main hospital building.

In order to reprovide Ward 3 within Ronas, not all staff facilities could be provided immediately alongside the bedded areas, with some Ward 3 staff areas having remain within the north side of the decanted Ward 3 area. It was also require both Chemo and Clinical Skills to be decanted, thus impacting more departments than necessary. Ensuring Ward 3 staff facilities are decanted alongside the bedded areas, **Option 2** is deemed the preferred decant solution.

### OPTION 1: Ward 3 into Ronas Ward



485.42m<sup>2</sup> Accommodated in Ronas Ward

42.87m<sup>2</sup> of staff facilities located on North Side of Ward 3, accessed via link corridor

### OPTION 2: Ward 3 into Portacabins



16no. 9940x3460mm Portacabins

550.28m<sup>2</sup>

## 6.1 Department Decants Clinical Skills Decant Options [208.52m<sup>2</sup>] [57.25m<sup>2</sup>]

Due to Maternity Option 1 being identified as the preferred decant solution, Clinical Skills will need to be temporarily relocated. As such, two options were identified.

Option 1 considered full relocation to temporary modular accommodation within the car park of the hospital.

Option 2 would split the existing facilities, with the Main Meeting Room being moved to SDEC on the ground floor of the Main Hospital Building, and the Male Locker Room being located within the north side of the decanted Ward 3 area. This would leave the remainder of Clinical Skills to be decanted to a reduced element of temporary modular accommodation within the car park of the hospital.


In both options, the accommodation located in temporary modular accommodation could potentially be situated on an upper level as this would be a staff only area and does not require direct access to the main hospital building.

With space at a premium within the car park decant zone, **Option 2** is deemed the preferred decant solution, potentially on an upper level following further investigation with modular accommodation providers.


### OPTION 1: Full Ronas Ward into Portacabins



### Meeting Room into SDEC



### Junior Doctors Office to North Side of Ward 3



Meeting Room into SDEC  
44.44m<sup>2</sup>

Junior Doctors Office to North Side of Ward 3  
28.28m<sup>2</sup>

Total 72.72m<sup>2</sup>

### OPTION 2: Clinical Skills into Portacabins



## 6.1 Department Decants

### Chemo Decant Options [192.56m<sup>2</sup>]

Three options were identified for the Chemo Department.


Option 1 considered relocation to temporary modular accommodation within the car park of the hospital.

Option 2 considered retaining Chemotherapy in it's current location within the 2nd floor ex Ronas Ward.

Option 3 considered relocation to a Mobile Infusion Unit within the car park of the hospital.

Staff highlighted that many patients value the privacy that the Chemo Department's current setting provides them with, which would be harder to offer in any of the suggested temporary locations, therefore **Option 2** is deemed the preferred solution.

#### OPTION 2: Chemo to Remain



Total Required Area to Remain in Chemo  
192.56m<sup>2</sup>

#### OPTION 1: Chemo into Portacabins



6no. 9940x3460mm  
Portacabins  
206.35m<sup>2</sup>

#### OPTION 3: Chemo into Mobile Units




3800x4490mm  
5 bay Infusion  
Mobile Unit  
55.6m<sup>2</sup>

## 6.1 Department Decants Outpatients Decant Options [432.289m<sup>2</sup>]

With Outpatients being located on the ground floor of the main hospital building, apart from some temporary propping already installed in the department to support the roof mounted scaffold above, there is no immediate requirement to decant these facilities. However, concerns have been raised that water ingress during the recladding works above could prove difficult to manage and therefore a potential decant should be considered. Whilst the Advising Contractor is investigating mitigation of risks of exposure during the works, consideration has been given to relocating the Outpatients department elsewhere. Being over 430sqm in area and with its co-dependency on other hospital services, to relocate off site is not viable. Therefore at present, the only solution is for full relocation to temporary modular accommodation within the car park of the hospital. With Ward 3 already relocated in the car park, not all clinical spaces can be accommodated at ground level. Given that Ward 3 is more likely to utilise patient trolleys to move patients to other parts of the Hospital building (Xray, MRI, Theatre), the current proposal would see Outpatients being positioned on the first floor of the temporary modular accommodation.

### Outpatients to Remain



Total Required Area to Remain in Outpatients  
432.289m<sup>2</sup>

### Outpatients into Portacabins



13no. 9940x3460mm Portacabins  
447.1m<sup>2</sup>

## 6.1 Department Decants ECG Decant Options [74.56m<sup>2</sup>]


Similar to Outpatients there is no immediate requirement to decant ECG unless water ingress during the recladding works above proves difficult to manage, therefore 2 options for potential decant should be considered.

Option 1 looked at possible relocation to SDEC, but the area available is not sufficient to accommodate ECG without incorporating additional space for adjoining rooms.

Option 2 considered relocation to temporary modular accommodation within the car park of the hospital.


Given the regular passage of patients between Ward 3 and ECG, it was felt that co-locating these departments would be the most effective solution during the decant period, therefore **Option 2** is deemed the preferred solution, should it be necessary.

ECG to Remain



Total Required Area to Remain in ECG  
74.56m<sup>2</sup>

### OPTION 1: ECG into SDEC



ECG into SDEC  
44.44m<sup>2</sup>  
30.12m<sup>2</sup> to be Accommodated Elsewhere

### OPTION 2: ECG into Portacabins



3no. 7540x3460mm Portacabins  
78.27m<sup>2</sup>

## 6.2 Decant Solutions Best Case Scenario

In this scenario, we have assumed potential issues with water ingress to the ground floor of the hospital during the recladding works will be designed out (solution developed in conjunction with Design Team and Advising Contractor). As such this Decant Solution combines options as follows

Maternity: Option 1 (pg. 38)

Renal: Option 3 (pg.39)

Ward 3: Option 2 (pg.40)


Clinical Skills: Option 2 with Meeting Rm retained / Junior Doctors relocated in GBH (pg 41)

Chemo: Option 2 (pg.42)


Outpatients and ECG to remain in their existing locations.

Aim is to locate all decanted space within a single storey block within the car park.

Maternity in Ronas Ward with Chemo, Meeting Room and Male Change to Remain



Junior Doctors Office into SDEC




Ward 3 and Clinical Skills into Portacabins  
Renal into Mobile unit in Carpark



- Maternity
- Renal
- Ward 3
- Clinical Skills
- Chemo

## 6.2 Decant Solutions Best Case Scenario Axonometric Diagram



## 6.2 Decant Solutions Worst Case Scenario

In this scenario, we have assumed the risk of water ingress to the ground floor of the hospital during the recladding works is deemed too high and therefore both Outpatients and ECG departments will need to be decanted too. As such this Decant Solution combines options as follows


- Maternity: Option 1 (pg. 38)
- Renal: Option 3 (pg.39)
- Ward 3: Option 2 (pg.40)
- Clinical Skills: Option 2 with Meeting Rm retained / Junior Doctors relocated in GBH (pg 41)
- Chemo: Option 2 (pg.42)
- Outpatients: relocated to portakabins (pg.43)
- ECG: Option 2 (pg.44)

A two storey solution will be required for the temporary accommodation block in the car park. That being the case, it will not be possible to locate all clinical rooms at ground floor.


In addition, the main corridor in the hospital will need temporary protection from water ingress for the duration of the recladding works.

- Outpatients
- ECG
- Maternity
- Renal
- Ward 3
- Clinical Skills
- Chemo

Maternity in Ronas Ward with Chemo, Meeting Room and Male Change to Remain



Junior Doctors Office into SDEC




Ground Floor Portacabin - Ward 3 and Clinical Skills  
Renal into Mobile Unit in Carpark



First Floor Portacabin - Outpatients and ECG



## 6.2 Decant Solutions Worst Case Scenario Axonometric Diagram



## 6.3 Temporary Accommodation

In order to progress the potential procurement of Temporary Modular / Mobile Accommodation for the decanted departments, NHS Shetland have been holding biweekly meetings with the Head of Procurement and Commodity Manager at NHS Scotland Procurement. This has identified 3 suppliers on the national frameworks, Portacabin, Vanguard Healthcare and Premier Modular. Initial kick-off meetings and follow-up scoping meetings have been held with all 3 suppliers to outline case of need, scope of works including SoA and site constraints. All 3 suppliers have indicated the timetable for delivery and execution is achievable although will be tight to meet the programme's early deadlines for permissions etc.

Issues raised to date (similar across all 3 suppliers):

- Area of external space for requirements of modular build;
- Derogations from standards (SHTM/ SHBN);
- Service integrations;
- Configurations/ layouts versus existing clinical spaces to allow potential residual resale value post contract;
- Length of contract.

This dialogue will continue over the coming months, with a Planning Submission target date of 6th June 2025.



Image Caption: Portakabin



Image Caption: Vanguard


An aerial photograph of a city street grid, rendered in a dark blue-grey color. A large, bold, white number '7' is overlaid on the left side of the image. A vertical white line is positioned to the right of the number '7', separating it from the word 'Appendices' which is written in a white, sans-serif font to the right of the line.

7

Appendices


# 7.1 Pre-Construction Programme

GBH Cladding, Master Programme, 25-03-2025, Rev 5 prepared by Thomson Gray (Project Manager)




# 7.2 Draft Construction Programme


Draft Programme V  
 04 12 Mar 25 prepared by  
 Robertson Construction  
 Group (Advising Contractor)



# 7.2 Draft Construction Programme



# 7.2 Draft Construction Programme



## 7.3 Project Risk Register

|                      |  |
|----------------------|--|
| <b>RISK REGISTER</b> |  |
| Project Title        | Gilbert Bain Cladding Remedials        |
| Revision No.         | Rev 2, 25-03-2025                      |
| Risk Champion        | David Wagstaff - NHSS Project Director |

GBH Cladding Risk Register  
25-03-2025 Rev 2 prepared  
by Thomson Gray (Project  
Manager)

| Ref No: | Type              | Workstream      | Risk Description   | Prior to Mitigation |              |                    | Mitigation   | Post Mitigation   |              |                    | Risk Owner | Risk/Mitigation Manager | Action Date | Comments   |
|---------|-------------------|-----------------|--|---------------------|--------------|--------------------|--|-------------------|--------------|--------------------|------------|-------------------------|-------------|--|
|         |                   |                 |  | Probability (1-5)   | Impact (1-5) | Risk Rating (1-25) |  | Probability (1-5) | Impact (1-5) | Risk Rating (1-25) |            |                         |             |  |
| 1       | Stakeholder       | Decant          | Inadequate Stakeholder Engagement or Design; May fail to engage with stakeholders or stakeholders are unable to dedicate adequate time for design. | 2                   | 4            | 8                  | Identify key stakeholders and negotiate appropriate time. Programming stakeholder time in advance in line with availability (6 weeks where possible for clinical staff).       | 1                 | 4            | 4                  | NHS        | David Wagstaff          |             |  |
| 2       | Design            | Decant/Cladding | Lack of existing site survey information at appointment of Contractor  | 3                   | 4            | 12                 | As built information is being sought. Some external surveys have been carried out  | 3                 | 4            | 12                 | NHS        | David Wagstaff          |             | 27-02-2025 Further decant and enabling surveys are required to old part of hospital. Asbestos register to be circulated. RONAS etc will need an asbestos refurb survey carried out. No intrusive work has been carried out.<br><br>Chosen option info from 360 will advise areas to be surveyed.<br><br>Services info may need to be reviewed but MRI project provided info for the west car park area. Water and drainage are known to be in this area. |
| 3       | Brief             | Decant/Cladding | Insufficient parking in car park following installation of temporary accommodation and contractor compound and safety cordon..                     | 4                   | 4            | 16                 | Alternative locations to be identified for temporary accommodation or parking..  | 2                 | 3            | 6                  | NHS        | David Wagstaff          |             | 27-02-2025 Parking to be designated for patients and visitors- off site parking may be required for staff, with transport plan (shuttle busses?). To be included in cost plan.<br>Contractor will need to provide transport/delivery schedule.   |
| 4       | Construction/Cost | Cladding        | Adverse weather delays work.   | 4                   | 4            | 16                 | Weather allowance to be incorporated into programme and costs  | 3                 | 4            | 12                 | NHS        | David Wagstaff          |             | 27-02-2025 Contractor to provide programme including weather allowances as tasks for deliveries and works.<br><br>Materials deliveries on ferries can be delayed by weather. Knock on delays for rebooking. This may affect temp accommodation and cladding deliveries.  |
| 5       | Site              | Cladding        | Ingress of rain water to ground floor once outer leaf of wall removed causes disruption to services in Outpatients department                      | 4                   | 5            | 20                 | Implications of removal of the outer leaf to be established during design and solution identified. Contractor to be engaged to assist in identifying a solution to this issue. | 2                 | 3            | 6                  | Contractor | TBC                     |             | 27-02-2025 Possible Tyvek layer may assist.  |
| 6       | Design            | Cladding        | Wind affects inner leaf of walls following removal of the outer leaf.  | 4                   | 3            | 12                 | Suitability of internal walls to be considered prior to exposing and suitable method of supporting identified.   | 2                 | 3            | 6                  | NHS        | David Wagstaff          |             | 27-02-2025 MM and Robertson to liaise and review.  |
| 7       | Contractor        | Cladding        | Works cause damage to ground floor roof.   | 3                   | 5            | 15                 | Contractor to review suitability RAMS for keeping water out of the areas of the building that remain.  | 1                 | 5            | 5                  | Contractor | TBC                     |             | 27-02-2025 Contractor RAMS to be developed.  |
| 8       | Site              | Decant          | Loss of continuity of (affected) clinical services during the relocation or construction phases.   | 4                   | 5            | 20                 | Robust planning of relocation strategy to be undertaken.   | 2                 | 5            | 10                 | NHS        | David Wagstaff          |             | 27-02-2025 Ongoing- regular meetings with stakeholders.  |
| 9       | Site              | Cladding        | Externally mounted plant serves unaffected areas of the building leading to additional works to maintain services.                                 | 3                   | 5            | 15                 | Detailed investigation and surveys to be carried out prior to works to determine the areas served by external items of plant (eg air conditioning plant, etc)                  | 2                 | 5            | 10                 | NHS        | David Wagstaff          |             | 27-02-2025 Engagement of M&E consultant to review.   |
| 10      | Cost              | Decant/Cladding | Costs of proposed solution are greater than cost estimate.   | 4                   | 3            | 12                 | Regular reviews to be undertaken to ensure cost estimate is valid.   | 3                 | 3            | 9                  | NHS        | David Wagstaff          |             | 27-02-2025 Unknowns will affect the costs, once site works start, once absolute detail is known.   |
| 11      | Programme         | Decant          | Decant strategy and procurement of accommodation takes longer than expected to develop leading to project delays.                                  | 4                   | 3            | 12                 | Early stakeholder engagement to be undertaken to develop robust strategy   | 2                 | 3            | 6                  | NHS        | David Wagstaff          |             | 27-02-2025 Procurement has started and supply chain engagement is underway to identify what accommodation is available.  |
| 12      | Site              | Decant/Cladding | Increased traffic movements during construction, including requirements for materials handling, etc., cause disruption.                            | 5                   | 4            | 20                 | Contractor to develop delivery schedule and programme deliveries outwith peak periods.   | 2                 | 5            | 10                 | Contractor | Contractor              |             | 27-02-2025 Traffic management plan. Peak period to be identified/ defined. Liaison with management team in hospital for future deliveries.<br><br>Blue light route to be protected at all times.   |

## 7.3 Project Risk Register

|                      |  |
|----------------------|--|
| <b>RISK REGISTER</b> |  |
| Project Title        | Gilbert Bain Cladding Remedials        |
| Revision No.         | Rev 2, 25-03-2025                      |
| Risk Champion        | David Wagstaff - NHSS Project Director |

| Ref No: | Type        | Workstream      | Risk Description  | Prior to Mitigation |              |                    | Mitigation  | Post Mitigation   |              |                    | Risk Owner       | Risk/Mitigation Manager   | Action Date | Comments   |
|---------|-------------|-----------------|---|---------------------|--------------|--------------------|---|-------------------|--------------|--------------------|------------------|---------------------------|-------------|--|
|         |             |                 |   | Probability (1-5)   | Impact (1-5) | Risk Rating (1-25) |   | Probability (1-5) | Impact (1-5) | Risk Rating (1-25) |                  |                           |             |  |
| 13      | Brief       | Decant          | Clinical Brief; May fail to define appropriately the clinical need resulting in change.   | 3                   | 4            | 12                 | Output specifications drawn up with users and signed off. Revisions will follow same process. Clinical leads to review clinical need based on service history and projected demand.                                     | 1                 | 4            | 4                  | NHS              | David Wagstaff            |             | 27-02-2025 Liaison ongoing   |
| 14      | Brief       | Decant          | Management of Expectations (Clinical Brief) Planned temporary facilities do not meet expectations of public, staff, clinicians, NHS, etc. Impacting reputation & Service Delivery Impact.   | 2                   | 3            | 6                  | Stakeholder engagement to be included in the programme.   | 1                 | 3            | 3                  | NHS              | David Wagstaff            |             | 27-02-2025 Liaison ongoing   |
| 15      | Site        | Decant          | Lack of power and other services for temporary clinical accommodation to accommodate all planned buildings resulting in programme delay and increased project cost.   | 2                   | 4            | 6                  | Load capacity check to be carried out on existing power supply to determine the availability of power for temporary facilities.   | 2                 | 4            | 3                  | NHS              | David Wagstaff            |             | 27-02-2025 M&E consultant to be engaged.   |
| 16      | Stakeholder | Decant/Cladding | NHS SCIM process including NDAP, KSAR, etc is not required for the project. Confirmation that this is not required should be confirmed. Current programme and scope assumes that there is no requirement to follow the SCIM process. Implementation of this process will have an impact on the programme. | 3                   | 3            | 9                  | Confirmation of requirements to be confirmed as soon as possible. NHS Assure to be included and updated throughout the programme. NHS Assure to be invited to meetings as required.                                     | 1                 | 3            | 3                  | NHS              | David Wagstaff            |             | 27-02-2025 Process does not exist but advice can be sought as required, via NHS Assure.  |
| 17      | Governance  | Decant/Cladding | Poor definition of roles, responsibilities and communication routes/paths leading to unfulfilled roles and responsibilities.  | 2                   | 3            | 6                  | Robust governance structures agreed. Terms of Reference, internal matrices and appointment documents in place for the project. PEP developed.   | 1                 | 3            | 3                  | NHS              | David Wagstaff            |             | 27-02-2025 PEP development underway.   |
| 18      | Design      | Decant/Cladding | Contractor may fail to identify and address site constraints (environmental concerns, ground conditions, public access, car parking, transport).  | 3                   | 3            | 9                  | Contractor to undertake site surveys to confirm site conditions and constraints and develop RAMS accordingly.   | 2                 | 2            | 4                  | Contractor       | Contractor                |             | 27-02-2025 Ongoing, and will be developed along side proposals.  |
| 19      | Governance  | Decant          | Fire Strategy does not match NHS Fire Officer and Building Control and Fire Code requirements.  | 2                   | 3            | 6                  | Fire strategy for temporary accommodation to be developed an approved prior to installation.  | 2                 | 3            | 6                  | Contractor       | Contractor                |             | 27-02-2025 Fire Consultant to be engaged when suitable info is available.  |
| 20      | Governance  | Decant/Cladding | NHS Scotland Assure do not support the project.   | 3                   | 4            | 12                 | NHSScotland Assure are providing support to NHS Shetland in an informal basis and no formal process is being followed (i.e. NDAP or KSAR) therefore there is no risk that NHSScotland Assure will affect the programme. | 1                 | 4            | 4                  | NHS              | David Wagstaff            |             | 19-03-2025 AW advised in an email that this is not a risk (see mitigation comment). Post mitigation risk rating probability reduced from 2 to 1.<br>27-02-2025 Advice to be sought as to whether this is relevant. |
| 21      | Site        | Decant/Cladding | Disruption to blue light routes.  | 2                   | 5            | 10                 | Contractor to plan deliveries (delivery schedule), suitable traffic management and clear supplier driver instructions to be developed if required.  | 1                 | 4            | 4                  | Contractor / NHS | Contractor/David Wagstaff |             | 27-02-2025 Contractor TM plan and site TM plan to be reviewed.   |
| 22      | Site        | Decant/Cladding | Issues with pedestrian / vehicle / cyclist interface and routes   | 3                   | 3            | 9                  | Ensure a robust Contractor traffic management plan is in place. Plan deliveries, suitable traffic management and clear supplier driver instructions to be developed.  | 2                 | 3            | 6                  | Contractor       | Contractor                |             | 27-02-2025 Contractor TM plan and site TM plan to be reviewed.   |
| 23      | Governance  | Decant/Cladding | Approval of Planning application by Shetland Islands Council may impact design, cost and/or programme   | 4                   | 3            | 12                 | Commence engagement as early as possible with Shetland Islands Council.   | 2                 | 3            | 6                  | NHS              | David Wagstaff            |             | 27-02-2025 Programme currently allows adequate time to achieve Planning Permission. 360 have submitted initial request to Planning with areas of decant and cladding proposals.                                    |
| 24      | Governance  | Decant/Cladding | Approval of Building Warrant application by Shetland Islands Council may impact design, cost and/or programme   | 4                   | 3            | 12                 | Commence engagement as early as possible with Shetland Islands Council.   | 2                 | 3            | 6                  | NHS              | David Wagstaff            |             | 27-02-2025 Programme has currently allows adequate time to achieve Building Control approval.  |
| 25      | Governance  | Decant/Cladding | Project Team Continuity including clinical team and project team (both client and lead advisor teams).  | 3                   | 3            | 9                  | Ensure handover processes are prepared and implemented. Documentation to detail decision making processes internally and find suitable alternatives.  | 3                 | 2            | 6                  | NHS              | David Wagstaff            |             |  |
| 26      | Governance  | Decant/Cladding | External communications management – reputational damage if not managed appropriately.  | 2                   | 3            | 6                  | Appointment of dedicated Comms Manager by NHS.  | 2                 | 2            | 4                  | NHS              | David Wagstaff            |             | 27-02-2025 Comms team/ corporate services manager will cover public comms.   |
| 27      | Governance  | Decant/Cladding | Business case not supported by Scottish Government due to wider public sector budgetary pressures   | 3                   | 5            | 15                 | Continued engagement with Scottish Government / NHS project board.  | 3                 | 5            | 15                 | NHS              | David Wagstaff            |             | 27-02-2025 Project supported to the end of March. To be reviewed.  |

## 7.3 Project Risk Register

|                      |  |
|----------------------|--|
| <b>RISK REGISTER</b> |  |
| Project Title        | Gilbert Bain Cladding Remedials        |
| Revision No.         | Rev 2, 25-03-2025                      |
| Risk Champion        | David Wagstaff - NHSS Project Director |

| Ref No: | Type         | Workstream      | Risk Description   | Prior to Mitigation |              |                    | Mitigation   | Post Mitigation   |              |                    | Risk Owner       | Risk/Mitigation Manager | Action Date | Comments   |
|---------|--------------|-----------------|--|---------------------|--------------|--------------------|--|-------------------|--------------|--------------------|------------------|-------------------------|-------------|--|
|         |              |                 |  | Probability (1-5)   | Impact (1-5) | Risk Rating (1-25) |  | Probability (1-5) | Impact (1-5) | Risk Rating (1-25) |                  |                         |             |  |
| 28      | Governance   | Decant/Cladding | Business case not supported by Scottish Government due to exceeding current budget allocation  | 2                   | 5            | 10                 | Initial Cost Plan currently being undertaken and OB Workshop completed. NHS to take updated costs once provided and progress through internal governance process.                | 2                 | 5            | 10                 | NHS              | David Wagstaff          |             | 27-02-2025 Unknowns will affect the costs, once site works start, once absolute detail is known.   |
| 29      | Governance   | Decant/Cladding | Delay in internal assurance and governance process impacts programme for delivery due to resource pressures  | 3                   | 4            | 12                 | Confirm NHS committee / meeting dates in advance including when inputs are due, and allocate realistic duration for governance processes within the programme.                   | 2                 | 4            | 8                  | NHS              | David Wagstaff          |             | 27-02-2025 Multiple Programme Boards. New clinical areas being established as part of decant will need to be passed through Infection control. Temp facilities will need allowance in programme for test commissioning, water testing period to be included in decant programme. Also to be included at the end of the programme prior to return to accommodation. |
| 30      | Brief        | Decant/Cladding | Employers Brief document hierarchy not suitably defined leading to ambiguity in Works Information  | 3                   | 3            | 9                  | Project Team will review the briefing information prior to issue to the Contractor. Hierarchy of documentation to be detailed within the Technical Brief or other documentation. | 2                 | 3            | 6                  | NHS              | David Wagstaff          |             | 27-02-2025 RIBA stage reports will be the brief for the project.<br><br>Info required following this will be determined by the procurement route.<br><br>If Board do not accept proposals then procurement will be delayed.  |
| 31      | Site         | Decant/Cladding | Potential access issues may be encountered preventing proposed site surveys to be progressed by Contractor   | 3                   | 3            | 9                  | Plan any surveys in advance and seek approval from necessary stakeholder.  | 1                 | 3            | 3                  | Contractor / NHS | TBC / David Wagstaff    |             |  |
| 32      | Site         | Decant/Cladding | Affect of temporary accommodation/contractors compounds (including services installation, vehicle movements, etc) on the car park surfacing, etc.  | 4                   | 3            | 12                 | Area to be monitored during works. Possible resurface/remedial works may be required.  | 2                 | 4            | 8                  | NHS              | David Wagstaff          |             | 27-02-2025 Dilapidation survey to be carried out prior to occupying these areas.   |
| 33      | Site         | Decant          | Workforce pressures may impact the nature of any decant proposals as staff teams can't be split across additional sites unless their numbers are increased – and the island location makes this more difficult to manage   | 4                   | 3            | 12                 | Where teams are to move, whole teams to be moved to same location and not split across locations. .  | 3                 | 3            | 9                  | NHS              | David Wagstaff          |             | 27-02-2025 360 to consider decant strategy.  |
| 34      | Site         | Decant          | Delayed patient discharges can account for up to 30% higher bed requirements. If we can reduce delayed discharges, we can reduce the number of beds required in the decant, therefore reduce the areas required. If delayed discharges go up, pressure on bed numbers for any decant will increase | 4                   | 3            | 12                 | Under review at present- to be updated.  | 4                 | 3            | 12                 | NHS              | David Wagstaff          |             |  |
| 35      | Contractor   | Decant/Cladding | On island availability and cost of accommodation for contractors may be a significant challenge  | 4                   | 3            | 12                 | Early booking of accommodation to be carried out by contractor.  | 3                 | 4            | 12                 | Contractor       | Contractor              |             |  |
| 36      | Contractor   | Decant/Cladding | Ferry space for deliveries may be a challenge.   | 4                   | 3            | 12                 | Early booking of ferries to be carried out by contractor.  | 3                 | 3            | 9                  | Contractor       | Contractor              |             |  |
| 37      | Contractor   | Cladding        | Noise and vibration may disrupt the hospital   | 5                   | 4            | 20                 | Works are close to patient areas. Noisy working times to be agreed with clinical staff on a daily basis<br><br>Decant of patients directly adjacent to work areas is planned.    | 2                 | 3            | 6                  | Contractor       | Contractor              |             |  |
| 38      | Contractor   | Cladding        | Patient privacy may disrupt the scheduling of the construction works   | 5                   | 4            | 20                 | Window film to be considered for privacy<br><br>Decant of patients directly adjacent to work areas is planned.   | 2                 | 3            | 6                  | Contractor       | Contractor              |             |  |
| 39      | Contractor   | Cladding        | Ward 3 Lift and thoroughfare must be maintained for ward access and contingency and evacuation purposes.   | 3                   | 4            | 12                 | Contractor RAMS to be developed to keep this area clear.<br><br>First floor roof access to be planned from external areas.   | 1                 | 3            | 3                  | Contractor       | Contractor              |             |  |
| 40      | Site         | Decant/Cladding | Inability to secure temporary staffing to free up capacity for the Clinical Lead to undertake planning, oversight, execution and delivery of the relocation of services across the site.   | 4                   | 4            | 16                 | NHS workig with agency, Hub North and NHS to source suitable candidate.  | 4                 | 4            | 16                 | NHS              | David Wagstaff          |             |  |
| 41      | Construction | Decant/Cladding | HSE or other statutory body intervention either planned or ad-hoc leading to delays/ changes to the project deliverables.  | 3                   | 4            | 12                 | Competent contractor to be engaged to ensure that works are carried out to current standards   | 1                 | 4            | 4                  | Contractor       | Contractor              |             |  |

## 7.3 Project Risk Register

|                      |  |
|----------------------|--|
| <b>RISK REGISTER</b> |  |
| Project Title        | Gilbert Bain Cladding Remedials        |
| Revision No.         | Rev 2, 25-03-2025                      |
| Risk Champion        | David Wagstaff - NHSS Project Director |

| Ref No: | Type   | Workstream      | Risk Description   | Prior to Mitigation |              |                    | Mitigation   | Post Mitigation   |              |                    | Risk Owner | Risk/Mitigation Manager | Action Date | Comments |
|---------|--------|-----------------|--|---------------------|--------------|--------------------|--|-------------------|--------------|--------------------|------------|-------------------------|-------------|----------|
|         |        |                 |  | Probability (1-5)   | Impact (1-5) | Risk Rating (1-25) |  | Probability (1-5) | Impact (1-5) | Risk Rating (1-25) |            |                         |             |          |
| 42      | Design | Decant/Cladding | Adherence to built environment guidance (SHTM's etc) leading to design/ execution delays and increased costs.                              | 3                   | 4            | 12                 | Areas will be relocated but standards may not always be met other than items such as fire, water quality, some areas of ventilation, etc. further discussion required with NHSS Assure | 3                 | 4            | 12                 | NHS        | David Wagstaff          |             |          |
| 43      | Site   | Decant          | Inability to secure a decant solution that meets the clinical and operational requirements of the organisation.                            | 5                   | 5            | 25                 | Early engagement with modular accommodation suppliers, clinical teams etc. Further discussions required  | 5                 | 5            | 25                 | NHS        | David Wagstaff          |             |          |
| 44      | Site   | Cladding        | The structural integrity risk associated with a delay caused by funding allocation and/ or inability to secure a clinical decant solution. | 5                   | 5            | 25                 | Structural support of the walls around the tower to be implemented and installed. Design solution to be sought and solution installed.   | 5                 | 5            | 25                 | NHS        | David Wagstaff          |             |          |
|         |        |                 |  |                     |              |                    |  |                   |              |                    |            |                         |             |          |
|         |        |                 |  |                     |              |                    |  |                   |              |                    |            |                         |             |          |
|         |        |                 |  |                     |              |                    |  |                   |              |                    |            |                         |             |          |

## 7.4 Statutory Authority Responses

### Planning Response Received 27.02.25

Dear Mrs Allan

I refer to your pre-application enquiry above, submitted in respect of alterations to part of the facade of the Gilbert Bain Hospital which is likely to result in approximately 1,093m<sup>2</sup> of replacement cladding and the provision of temporary hospital accommodation for patients in the form of temporary mobile units and/or portacabin type treatment units within the existing parking area serving the hospital for a period of approximately 1 year.

You have not specified the type of cladding system to be used on the exterior elevations, nor provided an indication of the number of treatment units/portacabins (nor dimensions) that may be required on site, however having considered Class 9C of The Town and Country Planning (General Permitted Development) (Scotland) Order 1992 (as amended) I can advise that full planning permission will be required for both elements of the development works you have described.

Although no dimensions of the existing parking area to be taken up with the mobile units has been provided, it would appear that this area to be used for decanting patients, albeit temporarily, would exceed 100sqm. Furthermore, the existing car park to be used for an alternative function also lies within 10 metres of the boundary of the curtilage of the premises and given that the proposal would result in a reduction in the space available for the parking and turning of vehicles, the proposal would not benefit from permitted development rights in this instance. The part of the works which relate to the recladding of part of the exterior of the building would exceed 4 metres above ground level in places and as such, full planning permission would also be required for that element of the works.

Given that these development are intrinsically linked, from a planning perspective, it would make sense to ensure both developments are included on the one planning application submission, however it is entirely up to your client as to how they wish to proceed, however as one part of the development work is entirely dependent on the other, it is likely that two separate applications for each component part would be assessed and determined at the same time.

Should your client wish to proceed with an application for this development, I would strongly advise that they contact the Council's Roads Service prior to any submission as parking capacity and accessibility in and around the Gilbert Bain Hospital is already somewhat constrained and the displacement of a further 25 spaces, albeit for a temporary period of approximately 1 year, is also likely to give cause for concern. Please also note that existing and proposed plans for each element of the proposed development will require to be submitted and appropriately scaled and dimensioned, with full details of the colour and material finishes also to be included.

I trust the above information is of use to you in the interim, however please note that my response constitutes informal officer advice only, which shall not prejudice the outcome of any application you subsequently make, nor any decision taken by the Planning Authority.

Regards

Dawn Stewart, BA, MA, MRTPI  
 Planning Officer – Development Management  
 Shetland Islands Council  
 Development Department  
 Planning Service  
 8 North Ness  
 Lerwick  
 Shetland  
 ZE1 0LZ

Tel: 01595 744817  
 Email: [dawn.stewart@shetland.gov.uk](mailto:dawn.stewart@shetland.gov.uk)

### Building Control Response Received 12.03.25



## Shetland Islands Council

Executive Manager: Iain S McDiarmid  
 Director: Neil Grant

Threesixty Architecture  
 The Garment Factory, 6th Floor  
 10 Montrose Street  
 Glasgow  
 G1 1RE

FAO Gillian Allan

Your Ref:  
 Our Ref: **PA/2025/002**

Planning  
 Development Services  
 8 North Ness Business Park  
 Lerwick  
 Shetland  
 ZE1 0LZ

Telephone: 01595 744293  
[www.shetland.gov.uk](http://www.shetland.gov.uk)

If calling please ask for:  
 Hannah Gillie  
 Business Support Officer  
[building.standards@shetland.gov.uk](mailto:building.standards@shetland.gov.uk)  
 Direct Dial: 01595 744815

Date: 5th March 2025

Dear Sir/Madam,

### The Building (Scotland) Act 2003

#### Building Standards Pre-application Enquiry

Your pre-application enquiry regarding 'Replacement of parts of defective external leaf of the building with new cladding, plus provision of temporary decant accommodation in the grounds of the hospital' at Gilbert Brain Hospital, Lerwick has been received and will be answered as quickly as possible by the next available duty officer.

In the meantime you may find further useful information about the building warrant system on our website at [www.buildingstandards.gov.uk/buildingstandards](http://www.buildingstandards.gov.uk/buildingstandards) and also on the Local Authority Building Standards Scotland (LABSS) website at [www.labss.org](http://www.labss.org).

Thank you.


Yours faithfully,  
*Hannah Gillie*

Hannah Gillie  
 Business Support Officer


## 7.5 Drawings

All levels and dimensions to be checked on site prior to construction / fabrication; report discrepancies immediately. Do not scale dimensions from this drawings. This drawing is copyright protected.

REVISION



— NHS Shetland Ownership Boundary



SCALE 1:1250



### PLANNING

| SCALE     | DATE   | DRAWN | CHECKED |
|-----------|--------|-------|---------|
| 1:1250@A3 | Jan'25 | GA    | DEA     |

PROJECT  
**Gilbert Bain Hospital**  
**Elevational Structural Issues**  
**for NHS Shetland**

DRAWING  
**Location Plan**  
**As Existing**

**Threesixty**  
**Architecture**  
 10 MONTROSE STREET  
 GLASGOW  
 G1 1RE  
 0141 229 7575  
 www.360architecture.com

DRAWING No.  
**24069A-10-001**

All levels and dimensions to be checked on site prior to construction / fabrication; report discrepancies immediately. Do not scale dimensions from this drawing. This drawing is copyright protected.

REVISION



| SCALE    | DATE   | DRAWN | CHECKED |
|----------|--------|-------|---------|
| 1:200@A1 | Jan'25 | HM    | GA      |

PROJECT  
**Gilbert Bain Hospital**  
 Elevational Structural Issues  
 for NHS Shetland

DRAWING  
**GROUND FLOOR PLAN**  
 AS EXISTING

**Threesixty**  
 Architecture  
 10 MONTROSE STREET  
 GLASGOW  
 G1 1RE

0141 229 7575  
 www.360architecture.com


DRAWING No.  
**24069A-10-003**

NOTES

ORIGINAL A1

All levels and dimensions to be checked on site prior to construction / fabrication; report discrepancies immediately. Do not scale dimensions from this drawings. This drawing is copyright protected.

REVISION



| SCALE    | DATE   | DRAWN | CHECKED |
|----------|--------|-------|---------|
| 1:200@A1 | Jan'25 | HM    | GA      |

PROJECT  
**Gilbert Bain Hospital**  
 Elevational Structural Issues  
 for NHS Shetland

DRAWING  
**FIRST FLOOR PLAN**  
 AS EXISTING




10 MONTROSE STREET  
 GLASGOW G1 1RE  
 0141 229 7575  
 www.360architecture.com

DRAWING No.  
**24069A-10-004**

All levels and dimensions to be checked on site prior to construction / fabrication; report discrepancies immediately. Do not scale dimensions from this drawings. This drawing is copyright protected.

REVISION



| SCALE    | DATE   | DRAWN | CHECKED |
|----------|--------|-------|---------|
| 1:200@A1 | Jan'25 | HM    | GA      |

PROJECT  
**Gilbert Bain Hospital**  
 Elevational Structural Issues  
 for NHS Shetland


DRAWING  
**SECOND FLOOR PLAN**  
 AS EXISTING

**Threesixty**  
 Architecture

10 MONTROSE STREET  
 GLASGOW G1 1RE | 0141 229 7575  
 www.360architecture.com

DRAWING No.  
**24069A-10-005**

All levels and dimensions to be checked on site prior to construction / fabrication; report discrepancies immediately. Do not scale dimensions from this drawings. This drawing is copyright protected.



| REVISIONS |        |       |         |
|-----------|--------|-------|---------|
| SCALE     | DATE   | DRAWN | CHECKED |
| 1:200     | Jan'25 | DA    | GA      |






PROJECT  
**Gilbert Bain Hospital**  
 Elevational Structural Issues  
 for NHS Shetland

DRAWING  
**Third Floor Plan**  
 As Existing

**Threesixty**  
 Architecture  
 10 MONTROSE STREET  
 GLASGOW G1 1RE  
 t 0141 229 7575  
 www.360architecture.co.uk

DRAWING No.  
**24069A-10-006**

**NOTES** ORIGINAL A0  
 All levels and dimensions to be checked on site prior to construction / fabrication; report discrepancies immediately. Do not scale dimensions from this drawing. This drawing is copyright protected.  
 REVISION



| SCALE   | DATE   | DRAWN | CHECKED |
|---|--------|-------|---------|
| 1:100@A0  | Jan'25 | GA    | DEA     |
| PROJECT   |        |       |         |
| Gilbert Bain Hospital<br>Elevational Structural Issues<br>for NHS Shetland  |        |       |         |
| DRAWING   |        |       |         |
| Elevations as existing (Sht 1 of 2)   |        |       |         |
| Threesixty<br>Architecture<br>10 MONTROSE STREET<br>GLASGOW<br>G1 1RE<br>0141 229 7575<br>www.360architecture.com |        |       |         |
| DRAWING No.   |        |       |         |
| 24069A-10-008   |        |       |         |

NOTES ORIGINAL A0


All levels and dimensions to be checked on site prior to construction / fabrication; report discrepancies immediately. Do not scale dimensions from this drawing. This drawing is copyright protected.

REVISION


61419  
Gilbert Bain Hospital  
Elevation 36  
Level (m)  
A.O.D




61419  
Gilbert Bain Hospital  
Elevation 37  
Level (m)  
A.O.D




61419  
Gilbert Bain Hospital  
Elevation 38  
Level (m)  
A.O.D



61419  
Gilbert Bain Hospital  
Elevation 39  
Level (m)  
A.O.D



Gilbert Bain Hospital, Lerwick



A0@1:100scale

| SCALE    | DATE   | DRAWN | CHECKED |
|----------|--------|-------|---------|
| 1:100@A0 | Jan'25 | GA    | DEA     |

PROJECT  
Gibert Bain Hospital  
Elevational Structural Issues  
for NHS Shetland

DRAWING  
Elevations as existing  
(Sht 2 of 2)

Threesixty  
Architecture

10 MONTROSE STREET  
GLASGOW  
G1 1RE  
0141 229 7575  
www.360architecture.com


DRAWING No.  
24069A-10-009

All levels and dimensions to be checked on site prior to construction / fabrication; report discrepancies immediately. Do not scale dimensions from this drawings. This drawing is copyright protected.

REVISION



Area Available for Decant Accommodation : 636.22m<sup>2</sup>



SCALE 1:200



PLANNING

| SCALE    | DATE   | DRAWN | CHECKED |
|----------|--------|-------|---------|
| 1:200@A3 | Jan'25 | OP    | GA      |

PROJECT

Gilbert Bain Hospital  
Elevational Structural Issues  
for NHS Shetland

DRAWING

Site Plan -  
Area Available for Decant



10 MONTROSE STREET  
GLASGOW  
G1 1RE

0141 229 7575  
www.360architecture.com

DRAWING No.

24069A-11-001

All levels and dimensions to be checked on site prior to construction / fabrication: report discrepancies immediately. Do not scale dimensions from this drawing. This drawing is copyright protected.

REVISION

|   |          |                    |    |    |
|---|----------|--------------------|----|----|
| A | 03.03.25 | Updated Room Names | OP | PH |
|---|----------|--------------------|----|----|

| DEPARTMENT AREAS (m <sup>2</sup> ) |                     |
|------------------------------------|---------------------|
| Dental                             | 83.85m <sup>2</sup> |
| Outpatients                        | 521.67 <sup>2</sup> |
| ECG                                | 59.48m <sup>2</sup> |
| C.T Scan                           | 80.58m <sup>2</sup> |



| SCALE    | DATE   | DRAWN | CHECKED |
|----------|--------|-------|---------|
| 1:200@A1 | Jan'25 | HM    | GA      |

PROJECT  
**Gilbert Bain Hospital**  
 Elevational Structural Issues for NHS Shetland

DRAWING  
**GROUND FLOOR PLAN**  
 IMPACTED AREAS

**Threesixty** Architecture  
 10 MONTROSE STREET  
 GLASGOW G1 1RE | 0141 229 7575  
 www.360architecture.com

DRAWING No.  
**24069A-11-002 A**


**NOTES** ORIGINAL A1

All levels and dimensions to be checked on site prior to construction / fabrication; report discrepancies immediately. Do not scale dimensions from this drawings. This drawing is copyright protected.

REVISION

|   |          |                    |    |    |
|---|----------|--------------------|----|----|
| A | 03.03.25 | Updated Room Names | OP | GA |
|---|----------|--------------------|----|----|

| DEPARTMENT AREAS (m <sup>2</sup> ) |                       |
|------------------------------------|-----------------------|
| Total Maternity                    | 458.24 m <sup>2</sup> |
| Renal                              | 155.27 m <sup>2</sup> |



| SCALE    | DATE   | DRAWN | CHECKED |
|----------|--------|-------|---------|
| 1:200@A1 | Jan'25 | HM    | GA      |

PROJECT  
**Gilbert Bain Hospital**  
 Elevational Structural Issues  
 for NHS Shetland

DRAWING  
**FIRST FLOOR PLAN**  
 IMPACTED AREAS

**Threesixty**  
 Architecture  
 10 MONTROSE STREET  
 GLASGOW G1 1RE | 0141 229 7575  
 www.360architecture.com

DRAWING No.  
**24069A-11-003 A**

**NOTES** ORIGINAL A1

All levels and dimensions to be checked on site prior to construction / fabrication; report discrepancies immediately. Do not scale dimensions from this drawings. This drawing is copyright protected.

REVISION  
A 03.03.25 Updated Room Names OP GA

| DEPARTMENT AREAS (m <sup>2</sup> ) |                       |
|------------------------------------|-----------------------|
| Ward 3                             | 611.36 m <sup>2</sup> |
| Chemo                              | 176.63 m <sup>2</sup> |
| Ronas                              | 296.03 m <sup>2</sup> |



| SCALE    | DATE   | DRAWN | CHECKED |
|----------|--------|-------|---------|
| 1:200@A1 | Jan'25 | HM    | GA      |

PROJECT  
**Gilbert Bain Hospital**  
 Elevational Structural Issues  
 for NHS Shetland


DRAWING  
**SECOND FLOOR PLAN**  
 IMPACTED AREAS

**Threesixty**  
 Architecture  
 10 MONTROSE STREET  
 GLASGOW G1 1RE | 0141 229 7575  
 www.360architecture.com

DRAWING No.  
**24069A-11-004 A**

All levels and dimensions to be checked on site prior to construction / fabrication; report discrepancies immediately. Do not scale dimensions from this drawings. This drawing is copyright protected.

| DEPARTMENT AREAS (m <sup>2</sup> ) |                       |
|------------------------------------|-----------------------|
| Third Floor                        | 142.04 m <sup>2</sup> |



| REVISIONS |        |       |         |
|-----------|--------|-------|---------|
| SCALE     | DATE   | DRAWN | CHECKED |
| 1:200@A1  | Jan'25 | OP    | GA      |




PROJECT  
**Gilbert Bain Hospital**  
 Elevational Structural Issues  
 for NHS Shetland

DRAWING  
**Third Floor Plan**  
 Impacted Areas

**Threesixty**  
 Architecture  
 10 MONTROSE STREET  
 GLASGOW  
 G1 1RE  
 t 0141 229 7575  
 www.360architecture.co.uk

DRAWING No.  
**24069A-11-005**




**NOTES** ORIGINAL A0  
 All levels and dimensions to be checked on site prior to construction / fabrication; report discrepancies immediately. Do not scale dimensions from this drawing. This drawing is copyright protected.  
 REVISION



| ELEVATION AREAS |                            |
|-----------------|----------------------------|
| Elevation 40    | 130.28m <sup>2</sup>       |
| Elevation 41    | 155.73m <sup>2</sup>       |
| Elevation 42    | 136.52m <sup>2</sup>       |
| Elevation 43    | 111.77m <sup>2</sup>       |
| Elevation 44    | 104.62m <sup>2</sup>       |
| <b>TOTAL</b>    | <b>638.92m<sup>2</sup></b> |

| EXTENT OF REPAIRS |   |
|-------------------|---|
|                   | Full Facade Replacement   |
|                   | Replace Lintels and Cills, Replace movement joints & render beads     |
|                   | Identify and Replace Areas of Bossed Render only                      |
|                   | Render removed, overcladding to cavity walls, replace lintels & cills |

Gilbert Bain Hospital, Lerwick



SCALE DATE DRAWN CHECKED  
 1:100@A0 Jan25 OP GA

PROJECT  
 Gilbert Bain Hospital  
 Elevational Structural Issues  
 for NHS Shetland


DRAWING  
 Affected Elevations -  
 extent of works (sheet 1 of 2)

**Threesixty**  
 Architecture

10 MONTROSE STREET  
 GLASGOW  
 G1 1RE 0141 229 7575  
 www.360architecture.com

DRAWING No.  
 24069A-11-007



**NOTES** ORIGINAL A0  
 All levels and dimensions to be checked on site prior to construction / fabrication; report discrepancies immediately. Do not scale dimensions from this drawing. This drawing is copyright protected.  
 REVISION



| ELEVATION AREAS |                            |
|-----------------|----------------------------|
| Elevation 36    | 204.13m <sup>2</sup>       |
| Elevation 37    | 102.31m <sup>2</sup>       |
| <b>TOTAL</b>    | <b>306.44m<sup>2</sup></b> |
| Elevation 38    | 55.69m <sup>2</sup>        |
| Elevation 39    | 91.92m <sup>2</sup>        |
| <b>TOTAL</b>    | <b>147.61m<sup>2</sup></b> |

| EXTENT OF REPAIRS |   |
|-------------------|---|
|                   | Full Facade Replacement   |
|                   | Replace Lintels and Cills, Replace movement joints & render beads     |
|                   | Identify and Replace Areas of Bossed Render only                      |
|                   | Render removed, overcladding to cavity walls, replace lintels & cills |

Gilbert Bain Hospital, Lerwick



A0@1:100scale

| SCALE    | DATE   | DRAWN | CHECKED |
|----------|--------|-------|---------|
| 1:100@A0 | Jan'25 | OP    | GA      |

PROJECT  
**Gilbert Bain Hospital**  
 Elevational Structural Issues  
 for NHS Shetland



DRAWING  
**Affected Elevations -**  
 Extent of works (Option 1)

**Threesixty**  
 Architecture

10 MONTROSE STREET  
 GLASGOW  
 G1 1RE  
 0141 229 7575  
 www.360architecture.com

DRAWING No.  
**24069A-11-008**



**NOTES** ORIGINAL A0  
 All levels and dimensions to be checked on site prior to construction / fabrication; report discrepancies immediately. Do not scale dimensions from this drawing. This drawing is copyright protected.  
 REVISION



| ELEVATION AREAS |                            |
|-----------------|----------------------------|
| Elevation 36    | 204.13m <sup>2</sup>       |
| Elevation 37    | 102.31m <sup>2</sup>       |
| <b>TOTAL</b>    | <b>306.44m<sup>2</sup></b> |
| Elevation 38    | 55.69m <sup>2</sup>        |
| Elevation 39    | 91.92m <sup>2</sup>        |
| <b>TOTAL</b>    | <b>147.61m<sup>2</sup></b> |

| EXTENT OF REPAIRS |   |
|-------------------|---|
|                   | Full Facade Replacement   |
|                   | Replace Lintels and Cills, Replace movement joints & render beads     |
|                   | Identify and Replace Areas of Bossed Render only                      |
|                   | Render removed, overcladding to cavity walls, replace lintels & cills |

Gilbert Bain Hospital, Lerwick




A0@1:100scale

**NOTE**  
 Extent of Replacement Works is subject to the outcome of more detailed investigations to be carried out by the Structural Engineer

| SCALE   | DATE   | DRAWN                                    | CHECKED |
|---|--------|--|---------|
| 1:100@A0  | Jan'25 | OP                                       | GA      |
| PROJECT   |        |  |         |
| Gilbert Bain Hospital<br>Elevational Structural Issues for NHS Shetland |        |  |         |
| DRAWING   |        |  |         |
| Affected Elevations - extent of works (Option 2)                        |        |  |         |
| Threesixty Architecture   |        |  |         |
| 10 MONTROSE STREET<br>GLASGOW<br>G1 1RE                                 |        | 0141 229 7575<br>www.360architecture.com |         |
| DRAWING No.   |        |  |         |
| 24069A-11-009   |        |  |         |

Internal Side



**DETAIL - Typical Slab Edge Proposed Interface - SECTION 1:5**


**Material Reference:**

1. 3mm Aluminium Cladding Cassette  
A1 Non-Combustible - Valcan Vitradual or equal - Secret fix, 15mm joints  
Finish: PVDF KYNAR 500 suitable for coastal location - Colour TBC
2. Proprietary Vertical Cladding Rails  
floor to floor span. Valcan Vitrafix system or equal to cladding sub-contractor design
3. Non-Combustible mineral wool insulation slabs.  
Rockwool rainscreen duoslab or equal to meet U-Value
4. 100mm Existing blockwork internal leaf wall to be retained .
5. Breather membrane
6. Existing concrete slab retained
7. Proprietary Valcan Vitrafix or equal cladding support channel, to be fixed to new horizontal steel mamber. Size TBC by cladding sub-contractor - Where applicable -Gap in-between insulation to be filled with non-combustible insulation to preserve thermal continuity.
8. min. 25mm Continuous vertical aerated cavity60/60 min. Horizontal firestopping suitable for ventilated rainscreen, Rockwool OSB or equal, with intumescent expanding edge.Firestopping around openings, compartments and separation lines
9. New cladding horizontal structural support, galvanised hot rolled to S.E design. Final position TBC. New horizontal structure to be fixed to existing columns to S.E design . Centres TBC. Thermal insulation from existing to be provided to avoid cold bridging
10. Aluminium flashing to match aluminium cladding.Finish: PVDF KYNAR 500 suitable for coastal location - Colour TBC
11. Existing/New lintel to be retained and made good to accommodate new windows
12. EPDM membrane overlap over breather membrane to cladding sub-contractor design
13. 60/60 FR Vertical full fill continuous rainscreen firestopping/cavity barrier at corners, around openings and at compartment lines. Max. cavity size 20 mt . Rockwool Firestop SP or equal
14. New UPVC Window, frame colour TBC. Windows to meet statutory U-Value as per table
15. Where possible, internal lining to be retained as per existing conditions, to be made good to accept new fenestration elements.
16. External leaf to be retained, render to be stripped, surface to be made good to accept new cladding
17. Existing block to be removed to allow for installation of new galv. structural outrigger to be fixed to existing concrete columns/walls
18. New cavity closer to be installed between existing masonry leaves upon removal of existing fenestration
19. Existing 200mm Concrete Wall retained, applicable to stair cores.
20. Cavity Tray/Weep Holes - Retention TBC - as part of the lintel replacing works

NOTES ORIGINAL A3

All levels and dimensions to be checked on site prior to construction / fabrication; report discrepancies immediately. Do not scale dimensions from this drawings. This drawing is copyright protected.

REVISION  
A 26.03.25 Legend revised. GP GA



**Key Plan 1:1000** Extents of Detail

**Targeted U-Values (statutory requirements to table 6.2.1)**  
**Building Control to confirm target:**

|                   |            |
|-------------------|------------|
| Walls:            | 0.21 W/m²K |
| Floors:           | 0.18 W/m²K |
| Roof:             | 0.16 W/m²K |
| Windows:          | 1.61 W/m²K |
| Pedestrian Doors: | 1.4 W/m²K  |

**STAGE 1**

| SCALE  | DATE   | DRAWN | CHECKED |
|--------|--------|-------|---------|
| 1:5@A3 | Jan'25 | GP    | GA      |


PROJECT  
**NHS Shetland  
Gilbert Bain Hospital  
External Remedial Works**

DRAWING  
**SECTION DETAIL - Slab edge  
Single Leaf Masonry Retained**

**Threesixty Architecture**  
10 MONTROSE STREET  
GLASGOW  
G1 1RE  
0141 229 7575  
www.360architecture.com

DRAWING No.  
**24069-21-101A**

Internal Side



**DETAIL 1/2 - Typical window head - SECTION 1:5**

**DETAIL 2/2 - Typical window cill - SECTION 1:5**


**Material Reference:**

1. 3mm Aluminium Cladding Cassette  
A1 Non-Combustible - Valcan Vitradual or equal - Secret fix, 15mm joints  
Finish: PVDF KYNAR 500 suitable for coastal location - Colour TBC
2. Proprietary Vertical Cladding Rails  
floor to floor span. Valcan Vitrafix system or equal to cladding sub-contractor design
3. Non-Combustible mineral wool insulation slabs.  
Rockwool rainscreen duoslab or equal to meet U-Value
4. 100mm Existing blockwork internal leaf wall to be retained .
5. Breather membrane
6. Existing concrete slab retained
7. Proprietary Valcan Vitrafix or equal cladding support channel, to be fixed to new horizontal steel member. Size TBC by cladding sub-contractor - Where applicable -Gap in-between insulation to be filled with non-combustible insulation to preserve thermal continuity.
8. min. 25mm Continuous vertical aerated cavity60/60 min. Horizontal firestopping suitable for ventilated rainscreen, Rockwool OSB or equal, with intumescent expanding edge.Firestopping around openings, compartments and separation lines
9. New horizontal structural support, galvanised hot rolled to S.E design.  
Final position TBC. New horizontal structure to be fixed to existing columns to S.E design . Centres TBC. Thermal insulation from existing to be provided to avoid cold bridging
10. Aluminium flashing to match aluminium cladding.Finish: PVDF KYNAR 500 suitable for coastal location - Colour TBC
11. Existing/New lintel to be retained and made good to accommodate new windows
12. EPDM membrane overlap over breather membrane to cladding sub-contractor design
13. 60/60 FR Vertical full fill continuous rainscreen firestopping/cavity barrier at corners, around openings and at compartment lines. Max. cavity size 20 mt . Rockwool Firestop SP or equal
14. New UPVC Window, frame colour TBC.  
Windows to meet statutory U-Value as per table
15. Where possible, internal lining to be retained as per existing conditions, to be made good to accept new fenestration elements.
16. External leaf to be retained, render to be stripped, surface to be made good to accept new cladding
17. Existing block to be removed to allow for installation of new galv. structural outrigger to be fixed to existing concrete columns/walls
18. New cavity closer to be installed between existing masonry leaves upon removal of existing fenestration
19. Existing 200mm Concrete Wall retained, applicable to stair cores.
20. Cavity Tray/Weep Holes - Retention TBC - as part of the lintel replacing works

NOTES ORIGINAL A3

All levels and dimensions to be checked on site prior to construction / fabrication; report discrepancies immediately. Do not scale dimensions from this drawings. This drawing is copyright protected.

| REVISION |  |
|----------|--|
| A        | 26.03.25 Material Legend Revised GP GA |



**Targeted U-Values (statutory requirements to table 6.2.1)**  
**Building Control to confirm target:**

|                   |            |
|-------------------|------------|
| Walls:            | 0.21 W/m²K |
| Floors:           | 0.18 W/m²K |
| Roof:             | 0.16 W/m²K |
| Windows:          | 1.61 W/m²K |
| Pedestrian Doors: | 1.4 W/m²K  |

**STAGE 1**


| SCALE  | DATE   | DRAWN | CHECKED |
|--------|--------|-------|---------|
| 1:5@A3 | Jan'25 | GP    | GA      |

PROJECT  
NHS Shetland  
Gilbert Bain Hospital  
External Remedial Works


DRAWING  
SECTIONAL DETAIL - Typical Cill and Head - Single Block Retained

**Threesixty Architecture**  
10 MONTROSE STREET  
GLASGOW  
G1 1RE  
0141 229 7575  
www.360architecture.com

DRAWING No.  
24069-21-102A



**DETAIL 1/2 - Typical Corner - PLAN**  
1:5



**DETAIL - Typical Window Jamb - PLAN**  
1:5

**Material Reference:**


1. 3mm Aluminium Cladding Cassette  
A1 Non-Combustible - Valcan Vitradual or equal - Secret fix, 15mm joints  
Finish: PVDF KYNAR 500 suitable for coastal location - Colour TBC
2. Proprietary Vertical Cladding Rails  
floor to floor span. Valcan Vitrafix system or equal to cladding sub-contractor design
3. Non-Combustible mineral wool insulation slabs.  
Rockwool rainscreen duoslab or equal to meet U-Value
4. 100mm Existing blockwork internal leaf wall to be retained .
5. Breather membrane
6. Existing concrete column retained
7. Proprietary Valcan Vitrafix or equal cladding support channel, to be fixed to new horizontal steel member. Size TBC by cladding sub-contractor - Where applicable -Gap in-between insulation to be filled with non-combustible insulation to preserve thermal continuity.
8. min. 25mm Continuous vertical aerated cavity 60/60 min. Horizontal firestopping suitable for ventilated rainscreen, Rockwool OSB or equal, with intumescent expanding edge. Firestopping around openings, compartments and separation lines
9. New horizontal structural support, galvanised hot rolled to S.E design.  
Final position TBC. New horizontal structure to be fixed to existing columns to S.E design . Centres TBC. Thermal insulation from existing to be provided to avoid cold bridging
10. Aluminium flashing to match aluminium cladding. Finish: PVDF KYNAR 500 suitable for coastal location - Colour TBC
11. Existing/New lintel to be retained and made good to accommodate new windows
12. EPDM membrane overlap over breather membrane to cladding sub-contractor design
13. 60/60 FR Vertical full fill continuous rainscreen firestopping/cavity barrier at corners, around openings and at compartment lines. Max. cavity size 20 mt . Rockwool Firestop SP or equal
14. New UPVC Window, frame colour TBC.  
Windows to meet statutory U-Value as per table
15. Where possible, internal lining to be retained as per existing conditions, to be made good to accept new fenestration elements.
16. External leaf to be retained, render to be stripped, surface to be made good to accept new cladding
17. Existing block to be removed to allow for installation of new galv. structural outrigger to be fixed to existing concrete columns/walls
18. New cavity closer to be installed between existing masonry leafs upon removal of existing fenestration
19. Existing 200mm Concrete Wall retained, applicable to stair cores.
20. Cavity Tray/Weep Holes - Retention TBC - as part of the lintel replacing works

**NOTES ORIGINAL A3**

All levels and dimensions to be checked on site prior to construction / fabrication; report discrepancies immediately. Do not scale dimensions from this drawings. This drawing is copyright protected.

REVISION

|   |          |                         |    |    |
|---|----------|-------------------------|----|----|
| A | 26.03.25 | Material Legend Revised | GP | GA |
|---|----------|-------------------------|----|----|



**Targeted U-Values (statutory requirements to table 6.2.1)**  
**Building Control to confirm target:**

|                   |            |
|-------------------|------------|
| Walls:            | 0.21 W/m²K |
| Floors:           | 0.18 W/m²K |
| Roof:             | 0.16 W/m²K |
| Windows:          | 1.61 W/m²K |
| Pedestrian Doors: | 1.4 W/m²K  |

**STAGE 1**

|        |        |       |         |
|--------|--------|-------|---------|
| SCALE  | DATE   | DRAWN | CHECKED |
| 1:5@A3 | Jan'25 | GP    | GA      |

PROJECT  
NHS Shetland  
Gilbert Bain Hospital  
External Remedial Works

DRAWING  
PLAN DETAIL - Typical Perimeter  
Single Blockwork Leaf Retained

**Threesixty Architecture**

10 MONTROSE STREET  
GLASGOW  
G1 1RE

0141 229 7575  
www.360architecture.com

DRAWING No.  
24069-21-103A


**Material Reference:**

1. 3mm Aluminium Cladding Cassette  
A1 Non-Combustible - Valcan Vitradual  
or equal - Secret fix, 15mm joints  
Finish: PVDF KYNAR 500 suitable for coastal  
location - Colour TBC
2. Proprietary Vertical Cladding Rails  
floor to floor span. Valcan Vitrafix system or equal  
to cladding sub-contractor  
design
3. Non-Combustible mineral wool insulation slabs.  
Rockwool rainscreen duoslab or equal to meet  
U-Value
4. 100mm Existing blockwork internal leaf wall  
to be retained .
5. Breather membrane
6. Existing concrete slab retained
7. Proprietary Valcan Vitrafix or equal cladding  
support channel, to be fixed to new horizontal  
steel mamber. Size TBC by cladding  
sub-contractor - Where applicable -Gap  
in-between insulation to be filled with  
non-combustible insulation to preserve  
thermal continuity.
8. min. 25mm Continuous vertical aerated  
cavity60/60 min. Horizontal firestopping  
suitable for ventilated rainscreen, Rockwool  
OSB or equal, with intumescent expanding  
edge.Firestopping around openings,  
compartments and separation lines
9. New horizontal structural support, galvanised  
hot rolled to S.E design.  
Final position TBC. New horizontal structure  
to be fixed to existing columns to S.E design .  
Centres TBC. Thermal insulation from  
existing to be provided to avoid cold bridging
10. Aluminium flashing to match aluminium  
cladding.Finish: PVDF KYNAR 500 suitable for  
coastal location - Colour TBC
11. Existing/New lintel to be retained and made  
good to accommodate new windows
12. EPDM membrane overlap over breather  
membrane to cladding sub-contractor design
13. 60/60 FR Vertical full fill continuous  
rainscreen firestopping/cavity barrier  
at corners, around openings and at  
compartment lines. Max. cavity size 20 mt .  
Rockwool Firestop SP or equal
14. New UPVC Window, frame colour TBC.  
Windows to meet statutory U-Value as per  
table
15. Where possible, internal lining to be retained  
as per existing conditions, to be made good to  
accept new fenestration elements.
16. External leaf to be retained, render to be  
stripped, surface to be made good to accept  
new cladding
17. Existing block to be removed to allow for  
installation of new galv. structural outrigger to  
be fixed to existing concrete columns/walls
18. New cavity closer to be installed between  
existing masonry leaves upon removal of  
existing fenestration
19. Existing 200mm Concrete Wall retained,  
applicable to stair cores.
20. Cavity Tray/Weep Holes - Retention TBC -  
as part of the lintel replacing works

NOTES ORIGINAL A3

All levels and dimensions to be checked on site prior to construction / fabrication; report discrepancies immediately. Do not scale dimensions from this drawings. This drawing is copyright protected.

| REVISION |   |
|----------|---|
| A        | 26.03.25 Material Legend Revised. GP GA |



**Targeted U-Values (statutory requirements to table 6.2.1)**  
**Building Control to confirm target:**

|                   |            |
|-------------------|------------|
| Walls:            | 0.21 W/m²K |
| Floors:           | 0.18 W/m²K |
| Roof:             | 0.16 W/m²K |
| Windows:          | 1.61 W/m²K |
| Pedestrian Doors: | 1.4 W/m²K  |

**STAGE 1**

| SCALE  | DATE   | DRAWN | CHECKED |
|--------|--------|-------|---------|
| 1:5@A3 | Jan'25 | GP    | GA      |

PROJECT  
NHS Shetland  
Gilbert Bain Hospital  
External Remedial Works


DRAWING  
SECTIONAL DETAIL - Typical Cill  
and Head -

**Threesixty Architecture**  
10 MONTROSE STREET  
GLASGOW  
G1 1RE  
0141 229 7575  
www.360architecture.com

DRAWING No.  
24069-21-104A

Internal Side

**DETAIL 1/2 - Typical window head - SECTION 1:5**



**DETAIL 2/2 - Typical window cill - SECTION 1:5**

notional projection line of existing columns

**Material Reference:**


1. 3mm Aluminium Cladding Cassette  
A1 Non-Combustible - Valcan Vitradual or equal - Secret fix, 15mm joints  
Finish: PVDF KYNAR 500 suitable for coastal location - Colour TBC
2. Proprietary Vertical Cladding Rails  
floor to floor span. Valcan Vitrafix system or equal to cladding sub-contractor design
3. Non-Combustible mineral wool insulation slabs.  
Rockwool rainscreen duoslab or equal to meet U-Value
4. 100mm Existing blockwork internal leaf wall to be retained .
5. Breather membrane
6. Existing concrete slab retained
7. Proprietary Valcan Vitrafix or equal cladding support channel, to be fixed to new horizontal steel member. Size TBC by cladding sub-contractor - Where applicable -Gap in-between insulation to be filled with non-combustible insulation to preserve thermal continuity.
8. min. 25mm Continuous vertical aerated cavity60/60 min. Horizontal firestopping suitable for ventilated rainscreen, Rockwool OSB or equal, with intumescent expanding edge.Firestopping around openings, compartments and separation lines
9. New horizontal structural support, galvanised hot rolled to S.E design.  
Final position TBC. New horizontal structure to be fixed to existing columns to S.E design . Centres TBC. Thermal insulation from existing to be provided to avoid cold bridging
10. Aluminium flashing to match aluminium cladding.Finish: PVDF KYNAR 500 suitable for coastal location - Colour TBC
11. Existing/New lintel to be retained and made good to accommodate new windows
12. EPDM membrane overlap over breather membrane to cladding sub-contractor design
13. 60/60 FR Vertical full fill continuous rainscreen firestopping/cavity barrier at corners, around openings and at compartment lines. Max. cavity size 20 mt . Rockwool Firestop SP or equal
14. New UPVC Window, frame colour TBC.  
Windows to meet statutory U-Value as per table
15. Where possible, internal lining to be retained as per existing conditions, to be made good to accept new fenestration elements.
16. External leaf to be retained, render to be stripped, surface to be made good to accept new cladding
17. Existing block to be removed to allow for installation of new galv. structural outrigger to be fixed to existing concrete columns/walls
18. New cavity closer to be installed between existing masonry leaves upon removal of existing fenestration
19. Existing 200mm Concrete Wall retained, applicable to stair cores.
20. Cavity Tray/Weep Holes - Retention TBC - as part of the lintel replacing works

NOTES ORIGINAL A3

All levels and dimensions to be checked on site prior to construction / fabrication; report discrepancies immediately. Do not scale dimensions from this drawings. This drawing is copyright protected.

REVISION

A 26.03.25 Material Legend Revised. GP GA



Key Plan 1:1000 Extents of Detail application

**Targeted U-Values (statutory requirements to table 6.2.1)**  
**Building Control to confirm target:**

|                   |            |
|-------------------|------------|
| Walls:            | 0.21 W/m²K |
| Floors:           | 0.18 W/m²K |
| Roof:             | 0.16 W/m²K |
| Windows:          | 1.61 W/m²K |
| Pedestrian Doors: | 1.4 W/m²K  |

**STAGE 1**

| SCALE  | DATE   | DRAWN | CHECKED |
|--------|--------|-------|---------|
| 1:5@A3 | Jan'25 | GP    | GA      |


PROJECT  
NHS Shetland  
Gilbert Bain Hospital  
External Remedial Works

DRAWING  
SECTIONAL DETAIL - Typical Cill and Head - Concrete Cores

**Threesixty Architecture**  
10 MONTROSE STREET  
GLASGOW  
G1 1RE  
0141 229 7575  
www.360architecture.com


DRAWING No.  
24069-21-105A

Internal Side




**DETAIL 1/2 - Typical window head - SECTION 1:5**

**DETAIL 2/2 - Typical window cill - SECTION 1:5**



**DETAIL 1/2 - Typical Corner - PLAN**  
1:5



**DETAIL - Typical Window Jamb - PLAN**  
1:5


**Material Reference:**

1. 3mm Aluminium Cladding Cassette  
A1 Non-Combustible - Valcan Vitradual or equal - Secret fix, 15mm joints  
Finish: PVDF KYNAR 500 suitable for coastal location - Colour TBC
2. Proprietary Vertical Cladding Rails  
floor to floor span. Valcan Vitrafix system or equal to cladding sub-contractor design
3. Non-Combustible mineral wool insulation slabs.  
Rockwool rainscreen duoslab or equal to meet U-Value
4. 100mm Existing blockwork internal leaf wall to be retained .
5. Breather membrane
6. Existing concrete slab retained
7. Proprietary Valcan Vitrafix or equal cladding support channel, to be fixed to new horizontal steel member. Size TBC by cladding sub-contractor - Where applicable -Gap in-between insulation to be filled with non-combustible insulation to preserve thermal continuity.
8. min. 25mm Continuous vertical aerated cavity60/60 min. Horizontal firestopping suitable for ventilated rainscreen, Rockwool OSB or equal, with intumescent expanding edge. Firestopping around openings, compartments and separation lines
9. New horizontal structural support, galvanised hot rolled to S.E design.  
Final position TBC. New horizontal structure to be fixed to existing columns to S.E design . Centres TBC. Thermal insulation from existing to be provided to avoid cold bridging
10. Aluminium flashing to match aluminium cladding. Finish: PVDF KYNAR 500 suitable for coastal location - Colour TBC
11. Existing/New lintel to be retained and made good to accommodate new windows
12. EPDM membrane overlap over breather membrane to cladding sub-contractor design
13. 60/60 FR Vertical full fill continuous rainscreen firestopping/cavity barrier at corners, around openings and at compartment lines. Max. cavity size 20 mt . Rockwool Firestop SP or equal
14. New UPVC Window, frame colour TBC.  
Windows to meet statutory U-Value as per table
15. Where possible, internal lining to be retained as per existing conditions, to be made good to accept new fenestration elements.
16. External leaf to be retained, render to be stripped, surface to be made good to accept new cladding
17. Existing block to be removed to allow for installation of new galv. structural outrigger to be fixed to existing concrete columns/walls
18. New cavity closer to be installed between existing masonry leaves upon removal of existing fenestration
19. Existing 200mm Concrete Wall retained, applicable to stair cores.
20. Cavity Tray/Weep Holes - Retention TBC - as part of the lintel replacing works

NOTES ORIGINAL A3

All levels and dimensions to be checked on site prior to construction / fabrication; report discrepancies immediately. Do not scale dimensions from this drawings. This drawing is copyright protected.

| REVISION |   |
|----------|---|
| A        | 26.03.25 Material Legend Revised. GP GA |



**Targeted U-Values (statutory requirements to table 6.2.1)**  
**Building Control to confirm target:**

|                   |            |
|-------------------|------------|
| Walls:            | 0.21 W/m²K |
| Floors:           | 0.18 W/m²K |
| Roof:             | 0.16 W/m²K |
| Windows:          | 1.61 W/m²K |
| Pedestrian Doors: | 1.4 W/m²K  |

**STAGE 1**

| SCALE  | DATE   | DRAWN | CHECKED |
|--------|--------|-------|---------|
| 1:5@A3 | Jan'25 | GP    | GA      |

PROJECT  
NHS Shetland  
Gilbert Bain Hospital  
External Remedial Works

DRAWING  
PLAN DETAIL - Typical Perimeter  
Double Blockwork Leaf Retained

**Threesixty Architecture**  
10 MONTROSE STREET  
GLASGOW  
G1 1RE  
0141 229 7575  
www.360architecture.com

DRAWING No.  
24069-21-107A



**Notes**

- All dimensions are in metres unless noted otherwise.
- All levels are in metres unless noted otherwise.

**Key to symbols**

- 2 nr. 220 x 47 (C24) Temporary Props at 1.1m centres

**Reference drawings**

- MMD-100106891 NH04-S-DR-00-02-001 - Second Floor Plan
- MMD-100106891 NH04-S-DR-00-03-001 - Third Floor Plan
- MMD-100106891 NH04-S-DR-00-XX-001 - Elevations (Sheet 1 of 2)
- MMD-100106891 NH04-S-DR-00-XX-002 - Temporary Propping Details and Elevations (Sheet 2 of 2)

**DRAFT**  
Date: 25-03-2025

| P1  | 03:25 | EW    | Preliminary Issue | NP     | JM    |
|-----|-------|-------|-------------------|--------|-------|
| Rev | Date  | Drawn | Description       | Ch'k'd | App'd |

**M MOTT MACDONALD**


Greenhead  
Lerwick  
Shetland  
ZE1 0PY  
United Kingdom  
T +44 (0)1595 695049  
F +44 (0)1595 693404  
W mottmac.com

**Client**  
NHS Shetland  
Gilbert Bain Hospital  
South Road  
Lerwick  
ZE1 0TB

**Title**  
Gilbert Bain Hospital Phase 1 Construction  
Re-Cladding of External Walls  
First Floor Plan - Props to Inner Leaf Walls

|             |           |     |              |             |    |
|-------------|-----------|-----|--------------|-------------|----|
| Designed    | N Pearson | NP  | Eng check    | A Stout     | AS |
| Drawn       | E Wishart | EW  | Coordination | N Pearson   | NP |
| Dwg check   | N Pearson | NP  | Approved     | J Moncrieff | JM |
| Scale at A1 | Status    | Rev | Security     |             |    |
| 1:125       | PRE       | P1  | STD          |             |    |

**Drawing Number**  
MMD-100106891 NH04-S-DR-00-01-001




GBH FIRST FLOOR  
SCALE 1:125

© Mott MacDonald Ltd  
This document is issued for the party which commissioned it and for specific purposes connected with the captioned project only. It should not be relied upon by any other party or used for any other purpose.  
We accept no responsibility for the consequences of this document being relied upon by any other party, or being used for any other purpose, or containing any error or omission which is due to an error or omission in data supplied to us by other parties.



GBH SECOND FLOOR  
SCALE 1:125

Temporary supports are subject to review for fire engineering requirements and may need to be fire protected or an alternative material to timber used for the supports



**Notes**

- All dimensions are in metres unless noted otherwise.
- All levels are in metres unless noted otherwise.

**Key to symbols**

- 2 nr. 220 x 47 (C24) Temporary Props at 1.1m centres

**Reference drawings**

- MMD-100106891 NH04-S-DR-00-01-001 - First Floor Plan
- MMD-100106891 NH04-S-DR-00-03-001 - Third Floor Plan
- MMD-100106891 NH04-S-DR-00-XX-001 - Elevations (Sheet 1 of 2)
- MMD-100106891 NH04-S-DR-00-XX-002 - Temporary Propping Details and Elevations (Sheet 2 of 2)

**DRAFT**

Date : 25-03-2025..

|     |       |       |                   |        |       |
|-----|-------|-------|-------------------|--------|-------|
| P1  | 03:25 | EW    | Preliminary Issue | NP     | JM    |
| Rev | Date  | Drawn | Description       | Ch'k'd | App'd |

**M M**

**MOTT MACDONALD**

Greenhead  
Lerwick  
Shetland  
ZE1 0PY  
United Kingdom  
T +44 (0)1595 695049  
F +44 (0)1595 693404  
W mottmac.com

Client  
**NHS Shetland  
Gilbert Bain Hospital  
South Road  
Lerwick  
ZE1 0TB**


Title  
**Gilbert Bain Hospital Phase 1 Construction  
Re-Cladding of External Walls  
Second Floor Plan - Props to Inner Leaf Walls**

|           |           |    |              |             |    |
|-----------|-----------|----|--------------|-------------|----|
| Designed  | N Pearson | NP | Eng check    | A Stout     | AS |
| Drawn     | E Wishart | EW | Coordination | N Pearson   | NP |
| Dwg check | N Pearson | NP | Approved     | J Moncrieff | JM |

|             |        |     |          |
|-------------|--------|-----|----------|
| Scale at A1 | Status | Rev | Security |
| 1:125       | PRE    | P1  | STD      |

Drawing Number  
**MMD-100106891 NH04-S-DR-00-02-001**

© Mott MacDonald Ltd  
This document is issued for the party which commissioned it and for specific purposes connected with the captioned project only. It should not be relied upon by any other party or used for any other purpose.  
We accept no responsibility for the consequences of this document being relied upon by any other party, or being used for any other purpose, or containing any error or omission which is due to an error or omission in data supplied to us by other parties.



**Notes**

- All dimensions are in metres unless noted otherwise.
- All levels are in metres unless noted otherwise.

**Key to symbols**

■ 2 nr. 220 x 47 (C24) Temporary Props at 1.1m centres

**Reference drawings**

MMD-100106891 NH04-S-DR-00-01-001 - First Floor Plan  
 MMD-100106891 NH04-S-DR-00-02-001 - Second Floor Plan  
 MMD-100106891 NH04-S-DR-00-XX-001 - Elevations (Sheet 1 of 2)  
 MMD-100106891 NH04-S-DR-00-XX-002 - Temporary Propping Details and Elevations (Sheet 2 of 2)

**DRAFT**  
 Date: 25-03-2025

| P1  | 03:25 | EW    | Preliminary Issue | NP     | JM    |
|-----|-------|-------|-------------------|--------|-------|
| Rev | Date  | Drawn | Description       | Ch'k'd | App'd |

**MOTT MACDONALD**

Greenhead  
 Lerwick  
 Shetland  
 ZE1 0PY  
 United Kingdom  
 T +44 (0)1595 695049  
 F +44 (0)1595 693404  
 W mottmac.com

**Client**


NHS Shetland  
 Gilbert Bain Hospital  
 South Road  
 Lerwick  
 ZE1 0TB

**Title**

Gilbert Bain Hospital Phase 1 Construction  
 Re-Cladding of External Walls  
 Third Floor Plan - Props to Inner Leaf Walls


|             |           |     |              |             |    |
|-------------|-----------|-----|--------------|-------------|----|
| Designed    | N Pearson | NP  | Eng check    | A Stout     | AS |
| Drawn       | E Wishart | EW  | Coordination | N Pearson   | NP |
| Dwg check   | N Pearson | NP  | Approved     | J Moncrieff | JM |
| Scale at A1 | Status    | Rev | Security     |             |    |
| 1:125       | PRE       | P1  | STD          |             |    |

Drawing Number  
**MMD-100106891 NH04-S-DR-00-03-001**




THIRD FLOOR PLAN  
 SCALE 1:125


© Mott MacDonald Ltd  
 This document is issued for the party which commissioned it and for specific purposes connected with the captioned project only. It should not be relied upon by any other party or used for any other purpose.  
 We accept no responsibility for the consequences of this document being relied upon by any other party, or being used for any other purpose, or containing any error or omission which is due to an error or omission in data supplied to us by other parties.




ELEVATION 40  
FOUR STOREY WEST ELEVATION  
SCALE 1:50



ELEVATION 41  
FOUR STOREY SOUTH ELEVATION  
SCALE 1:50



ELEVATION 42  
FOUR STOREY EAST ELEVATION  
SCALE 1:50



GILBERT BAIN HOSPITAL  
ELEVATION LOCATION PLAN  
SCALE 1:500

Temporary supports are subject to review for fire engineering requirements and may need to be fire protected or an alternative material to timber used for the supports

Notes

1. All dimensions are in metres unless noted otherwise.
2. All levels are in metres unless noted otherwise.

Key to symbols

--- 2 nr. 220 x 47 (C24) Temporary Props at 1.1m centres

Reference drawings

MMD-100106891 NH04-S-DR-00-01-001 - First Floor Plan  
 MMD-100106891 NH04-S-DR-00-02-001 - Second Floor Plan  
 MMD-100106891 NH04-S-DR-00-03-001 - Third Floor Plan  
 MMD-100106891 NH04-S-DR-00-XX-002 - Temporary Propping Details and Elevations (Sheet 2 of 2)

**DRAFT**  
Date: 25-03-2025

| P1  | 03:25 | EW    | Preliminary Issue | NP     | JM    |
|-----|-------|-------|-------------------|--------|-------|
| Rev | Date  | Drawn | Description       | Ch'k'd | App'd |

**MOTT MACDONALD**

Greenhead  
Lerwick  
Shetland  
ZE1 0PY  
United Kingdom  
T +44 (0)1595 695049  
F +44 (0)1595 693404  
W mottmac.com

Client  
**NHS Shetland**  
Gilbert Bain Hospital  
South Road  
Lerwick  
ZE1 0TB


Title  
Gilbert Bain Hospital Phase 1 Construction  
Re-Cladding of External Walls  
Elevations (Sheet 1 of 2) - Props to Inner Leaf Walls

|             |           |     |              |             |    |
|-------------|-----------|-----|--------------|-------------|----|
| Designed    | N Pearson | NP  | Eng check    | A Stout     | AS |
| Drawn       | E Wishart | EW  | Coordination | N Pearson   | NP |
| Dwg check   | N Pearson | NP  | Approved     | J Moncrieff | JM |
| Scale at A1 | Status    | Rev | Security     |             |    |
| 1:50        | PRE       | P1  | STD          |             |    |

Drawing Number  
**MMD-100106891 NH04-S-DR-XX-001**


© Mott MacDonald Ltd  
This document is issued for the party which commissioned it and for specific purposes connected with the captioned project only. It should not be relied upon by any other party or used for any other purpose.  
We accept no responsibility for the consequences of this document being relied upon by any other party, or being used for any other purpose, or containing any error or omission which is due to an error or omission in data supplied to us by other parties.





ELEVATION 43  
FOUR STOREY NORTH ELEVATION  
SCALE 1:50

Temporary supports are subject to review for fire engineering requirements and may need to be fire protected or an alternative material to timber used for the supports



GILBERT BAIN HOSPITAL  
ELEVATION LOCATION PLAN  
SCALE 1:500

- Notes
- All dimensions are in metres unless noted otherwise.
  - All levels are in metres unless noted otherwise.

- Key to symbols
- 2 nr. 220 x 47 (C24) Temporary Props at 1.1m centres

- Reference drawings
- MMD-100106891 NH04-S-DR-00-01-001 - First Floor Plan
  - MMD-100106891 NH04-S-DR-00-02-001 - Second Floor Plan
  - MMD-100106891 NH04-S-DR-00-03-001 - Third Floor Plan
  - MMD-100106891 NH04-S-DR-00-XX-001 - Elevations (Sheet 1 of 2)

**DRAFT**  
Date: 25-03-2025

| P1  | 03:25 | EW    | Preliminary Issue | NP     | JM    |
|-----|-------|-------|-------------------|--------|-------|
| Rev | Date  | Drawn | Description       | Ch'k'd | App'd |

**MOTT MACDONALD**

Greenhead  
Lerwick  
Shetland  
ZE1 0PY  
United Kingdom  
T +44 (0)1595 695049  
F +44 (0)1595 693404  
W mottmac.com

Client  
**NHS Shetland  
Gilbert Bain Hospital  
South Road  
Lerwick  
ZE1 0TB**


Title  
**Gilbert Bain Hospital Phase 1 Construction  
Re-Cladding of External Walls  
Temporary Propping Details and  
Elevations (Sheet 2 of 2) - Props to  
Inner Leaf Walls**

|             |           |     |              |             |    |
|-------------|-----------|-----|--------------|-------------|----|
| Designed    | N Pearson | NP  | Eng check    | A Stout     | AS |
| Drawn       | E Wishart | EW  | Coordination | N Pearson   | NP |
| Dwg check   | N Pearson | NP  | Approved     | J Moncrieff | JM |
| Scale at A1 | Status    | Rev | Security     |             |    |
| 1:50; 1:20  | PRE       | P1  | STD          |             |    |

Drawing Number  
**MMD-100106891 NH04-S-DR-XX-002**




ELEVATION 44  
THREE STOREY SOUTH ELEVATION  
SCALE 1:50



TEMPORARY PROPS TO INNER LEAF BLOCKWORK WALLS  
SECTION  
SCALE 1:20



© Mott MacDonald Ltd  
This document is issued for the party which commissioned it and for specific purposes connected with the captioned project only. It should not be relied upon by any other party or used for any other purpose.  
We accept no responsibility for the consequences of this document being relied upon by any other party, or being used for any other purpose, or containing any error or omission which is due to an error or omission in data supplied to us by other parties.



**NOTES**

1. This drawing is to be read in conjunction with the preliminary report produced by Callidus Design detailing the proposed interface between the building structure and the MSE services.


|   |                                 |     |     |          |
|---|---------------------------------|-----|-----|----------|
| B | OUTDOOR UNIT REFERENCES UPDATED | GGG | NAC | 19.03.25 |
| A | INITIAL ISSUE                   | GGG | NAC | 10.03.25 |

Gilbert Bain Hospital, Lerwick  
Proposed External Cladding Installation  
Interface with MSE Services

callidus design limited  
Law House  
Fairbairn Place  
Livingston  
EH54 6TN  
Tel: 01506 418188

|   |        |           |
|---|--------|-----------|
| 790-ME200   | GGG    | DOB       |
| TSL0790   | MAR 25 | 1:50 @ A1 |
| First Floor<br>Maternity & Renal Unit<br>MSE Service Penetrations |        |           |
| 790 (5-) ME 200   | B      |           |

**FOR DISCUSSION**



CALLIDUS DESIGN LIMITED SHALL HAVE NO LIABILITY FOR ANY PART OF THE DRAWING OR FOR THE WORK WHICH HAS BEEN COMPLETED UNLESS IT IS CONTRACTUALLY OBLIGED TO DO SO.

ALL DIMENSIONS SHOWN IN THIS DRAWING ARE IN METERS UNLESS OTHERWISE SPECIFIED.

NO PART OF THIS DRAWING IS TO BE USED FOR CONSTRUCTION UNLESS IT IS APPROVED IN WRITING BY THE ARCHITECT OR HIS DELEGATED AUTHORITY.

**NOTES**

- This drawing is to be used in conjunction with the preliminary report produced by Callidus Design Limited. The architect reserves the right to amend the building structure and the M&E services.

A INITIAL ISSUE GCS MAC 10/01/25

Gilbert Bain Hospital, Lerwick  
Proposed External Cladding Installation  
Interface with M&E Services



callidus design limited  
Law House  
Fairbairn Place  
Livingston  
EH54 6TN  
Tel: 01506 418188

|                       |  |       |        |        |      |      |      |   |
|-----------------------|--|-------|--------|--------|------|------|------|---|
| PROJECT NO:           | 790-ME-400                                     | DATE: | MAR 25 | SCALE: | 1:50 | REV: | A    |   |
| PROJECT NAME:         | Third Floor Plantroom M&E Service Penetrations |       |        |        |      |      |      |   |
| PROJECT NO:           | 790 (5-) ME 400                                | DATE: |        |        |      |      | REV: | A |
| <b>FOR DISCUSSION</b> |  |       |        |        |      |      |      |   |

 Threesixty  
Architecture

[www.360architecture.com](http://www.360architecture.com)

**Certified**



**Corporation**